BILL OF QUANTITIES

ICF KIT · CONCRETE · LABOUR

BROMFELDE CORNER, 25 BROMFELDE ROAD, CLAPHAM

6 Flats (GF + 1F + 2F + attic) · 25 Bromfelde Road / Union Road, London SW4 6PP · ENGLAND

Quotation Reference	ES26-087
Project	Bromfelde Corner, 25 Bromfelde Road, Clapham
House Type	6 flats, corner block: 6in XR35 external walls + 6in Standard separating walls, FB + GF / 1F / 2F + 3F eaves / party wall, precast B&B floors (by others), cut roofs, natural slate
Client	JAUS (via Tremco CPG UK)
Site Address	25 Bromfelde Road / Union Road, London SW4 6PP
BOQ Issued	02 November 2026
BOQ Reference	BOQ-ES26-087-001
Prepared by	Tom Smith — BuildEase Manager, Nudura UK
Issued by	Tremco Construction Products Group
Currency	Pound Sterling (GBP) · VAT at 20%
Measurement Convention	RICS New Rules of Measurement (NRM2)

IMPORTANT NOTICE — DISCLAIMER

- This Bill of Quantities is supplied in good faith based on the BuildEase take-off models for Bromfelde Corner, 25 Bromfelde Road, Clapham and the associated Tremco CPG quotation.
- ALL QUANTITIES SHOULD BE INDEPENDENTLY CHECKED AND VERIFIED BY THE PROJECT QS / QUANTITY SURVEYOR before tender submission, ordering or contract award.
- This BOQ does NOT include an external render / finish allowance. Any render, coatings or external wall finish must be measured and priced separately.
- Section C (Concrete) volumes are geometric voids — allow ~3% web displacement deduction and ~5% wastage on top when ordering ready-mix.
- Section D (Labour) day estimates are scaled proportionately from a reference project; actual gang productivity will vary with site conditions, weather and trade experience.
- BuildEase, Tremco Construction Products Group and Nudura UK accept no liability for tender or contract outcomes arising from the use of these figures. If in doubt — ask.
- Contact: Tom Smith — BuildEase Manager, Nudura UK — for clarification on any quantity or rate basis in this document.

ENGLAND: the design must satisfy the Building Regulations 2010 (Approved Documents A-S) - building control by LABC / an approved inspector; NOT the Scottish technical handbooks. Building height (ADB Diagram D6, to the floor of the top storey): the 3F (Flat 5 attic) FFL is 8,229.6 above the GF FFL, ~8.38 m above the lowest adjoining ground (ground ASSUMED ~150 below GF FFL all round - to be confirmed on a measured survey) - BELOW 11 m (margin ~2.6 m), so the 11-18 m fire band (ADB B4 external-wall materials, sprinklers in new blocks of flats) does not apply. 4 storeys incl. the attic: the LABC Warranty technical manual caps ICF at 3 storeys unless an independent engineer inspects each pour (pre-pour) and signs off - the warranty provider must confirm. Flats = Consequence Class 2A (Approved Document A): floor-to-wall ties / anchorage are engineer-designed (outside the manufacturer tables).

NOT FOR CONSTRUCTION. The four "floor" slots of the programme are precast beam & block floors BY OTHERS; beams, blocks, screeds, craneage and the roof terrace are NOT in this ICF BOQ (coordination quantities in the finishes package Bill 6). Engineer to design: the indicative steels S1 / T1 / T2 (incl. the TRANSFER beams under the 1F north wall and the wing east wall over GF Flat 2), the B&B floors (beam supplier), the floor-to-wall ties (Class 2A), the roof (unpropped hip heads, room-in-roof at 3F) and the strip footing.


CONTENTS

Section	Description	Sheet	Status	
	Cover & Project Information	**Cover**		
	Contents	**Contents**		
	Indicative Programme (Gantt)	**Programme**	*Information*	
	Summary of Tender Pricing	**Summary**		
A	Preliminaries	**A_Preliminaries**	*Contractor priced*	
B	ICF Kit Supply	**B_ICF_Supply**	*Pre-priced*	
C	Concrete Supply, Pump & Placement	**C_Concrete**	*Contractor priced*	
D	Labour — ICF, Floors & Roofs	**D_Labour**	*Contractor priced*	
F	Reference Data (informative only)	**F_Reference**	—	

PROG · INDICATIVE INSTALL PROGRAMME — RESOURCE-LEVELLED, ONE COLUMN PER WORKING DAY

Group-by-group sequential build with a staggered start between groups. ICF install + snag + pour cycles, intermediate floors and roof structure are completed before moving on. Resourcing and durations below are indicative and must be validated by site management. Render / external finish is NOT included in this programme.

Group	Plots	Forms	Weeks	Start wk
Bromfelde Corner	1	709	10	1



LEGEND

	ICF walls — first lift: FB foundation (erection, snag & pour)
	ICF walls — L1 / L2 / L3 / L4 (each after the B&B floor below it)
	Concrete pour — sized at 60 m3 per pump-day, ICF crew attends, pump on site
	Curing — 2 working days after each pour, inside each 2-week floor
	Floor slots — GF B&B after FB, 1F after L1, 2F after L2, 3F after L3 (by others, a 1-day slot at the end of each 2-week floor)
	Roof structure (cut roofs, main + wing), after the 3F pour

RESOURCING

- 1 ICF crews of 8 trained installers (each crew = 2 four-man gang-equivalents) erect the wall lifts, moving to the next ready block while a floor is fitted; 1 joinery crew of 3 fits every intermediate floor and roof (2 weeks per floor on this project (each lift: ICF, pour, cure, floor slot); the 'floors' here are the GF / 1F / 2F / 3F precast beam & block floors (by others - programme slots, the joinery crew attends)). Programme is resource-levelled day by day (white = block waiting for a crew).

- Total ICF site programme: 10 working weeks (ICF erection, floors and roofs). Section A Preliminaries are quantified against this 10-week programme.

- EXTERNAL RENDER / FINISH IS EXCLUDED from this BOQ and this programme. Where a render system is later specified, allow a separate workstream — per BBA guidance, render cannot begin until the concrete core has cured for a minimum of 28 days after the final pour.

- Concrete pump booked on the pour days for each group (see Section C).

- Lead time for BuildEase Pre-Cut Service: 5–6 weeks from order placement; procurement runs in parallel with mobilisation.

- Programme estimates are provided in good faith and must be verified by the project / site management team.

- ENGLAND: the design must satisfy the Building Regulations 2010 (Approved Documents A-S) - building control by LABC / an approved inspector; NOT the Scottish technical handbooks. Building height (ADB Diagram D6, to the floor of the top storey): the 3F (Flat 5 attic) FFL is 8,229.6 above the GF FFL, ~8.38 m above the lowest adjoining ground (ground ASSUMED ~150 below GF FFL all round - to be confirmed on a measured survey) - BELOW 11 m (margin ~2.6 m), so the 11-18 m fire band (ADB B4 external-wall materials, sprinklers in new blocks of flats) does not apply. 4 storeys incl. the attic: the LABC Warranty technical manual caps ICF at 3 storeys unless an independent engineer inspects each pour (pre-pour) and signs off - the warranty provider must confirm. Flats = Consequence Class 2A (Approved Document A): floor-to-wall ties / anchorage are engineer-designed (outside the manufacturer tables).

• Programme: 2 weeks per floor on this project - the FB, GF, 1F, 2F and 3F lifts are each one 2-week block (ICF erection 6 days, pour, cure, then the floor slot); the roof follows the 3F pour. Every floor is PRECAST BEAM & BLOCK BY OTHERS (beam supplier / groundworker with a crane; the joinery crew attends): GF 150 B&B + 150 insulation + 50 screed (top of screed = FFL); 1F / 2F / 3F 150 B&B + 100 concrete topping + 25 levelling screed. The beams bear on the ICF core (inner panel cut down at the bearing course - ICF erector coordination). Floor beams, blocks, screeds and their craneage are NOT in this ICF BOQ (coordination quantities in the finishes package Bill 6).

• Build sequence (no client programme issued): FB foundation (2 courses on the strip footing by others) -> pour -> GF B&B floor -> L1 GF walls (6 courses) -> pour -> 1F B&B floor (incl. the roof terrace over GF Flat 2; indicative transfer steels T1 / T2 by the engineer) -> L2 1F walls -> pour -> 2F B&B floor -> L3 2F walls -> pour -> 3F B&B floor -> L4 3F eaves walls (cut at 9,144) + the NE party wall to 11,430 -> pour -> roof (cut roofs C24 @ 600, natural slate 33 deg).

• ICF pours sized at 60 m3 per pump per day from each lift's own concrete volume.

• PROGRAMME (BOQ Builder sheet 'Programme', 1 ICF crew of 8 + 1 joinery crew of 3): 2 WEEKS PER FLOOR - FB, GF, 1F, 2F and 3F each one 2-week block (ICF erection + snag 6 days, pour 1, cure 2, floor slot 1; the roof after the 3F pour): 50 working days = 10 weeks. Sequence: ICF FB d0-6; pour d6-7; cure d7-9; GF precast beam & block floor d9-10; ICF L1 d10-16; pour d16-17; cure d17-19; 1F B&B floor d19-20; ICF L2 d20-26; pour d26-27; cure d27-29; 2F B&B floor d29-30; ICF L3 d30-36; pour d36-37; cure d37-39; 3F B&B floor d39-40; ICF L4 d40-46; pour d46-47; cure d47-49; roof d49-50. ICF concrete 111.43 m3 (geometric, 709 ordered forms: FB 12.46 / L1 31.95 / L2 32.80 / L3 24.64 / L4 9.57) in 5 pump days. ALIGNMENT: the proposal prices 4 stillages x 10 weeks hire (GBP 3,200.00); on this programme the alignment is needed from the first ICF lift (FB, day 0) to the last pour (L4, day 47) = 10 weeks on hire - the same as priced. The proposal prices the alignment hire for this programme.

• Site access: corner plot on residential streets in Clapham (London) - articulated delivery access, unloading and any road / parking suspension by the contractor for the 3 deliveries (33 pallets + 4 alignment stillages); a transfer to smaller vehicles is not included.

SUMMARY OF TENDER PRICING

Section totals are carried forward from each Bill section. Pre-priced columns show values from the associated Tremco CPG quotation; contractor-priced columns populate automatically when rates are entered in the section sheets. This BOQ excludes external render.

Section	Description	Pre-priced (£)	Contractor-priced (£)	Section Total (£)	
A	Preliminaries		£0.00	**£0.00**	
B	ICF Kit Supply	£50,343.06		**£50,343.06**	
C	Concrete Supply, Pump & Placement		£0.00	**£0.00**	
D	Labour — ICF, Floors & Roofs		£0.00	**£0.00**	
	NET TOTAL (excluding VAT)	**£50,343.06**	**£0.00**	**£50,343.06**	
	VAT @ 20%			£10,068.61	
	GRAND TOTAL (inclusive of VAT)			**£60,411.67**	

SIGNATURES

Priced by					
Tendered by					
Approved by					

A · PRELIMINARIES

Items priced per working week against the site programme total of 10 weeks (see Programme sheet). Quantities are pre-populated; the contractor inserts the weekly rate.

Ref	Description	Unit	Qty	Rate (£)	Total (£)
A.1	Site set-up, fencing, signage, induction & welfare establishment	item	1		£0.00
A.2	Welfare facilities — canteen, drying, toilets (hire)	wk	10		£0.00
A.3	Contract management & site supervision	wk	10		£0.00
A.4	Health & Safety, RAMS, CDM consultancy	wk	10		£0.00
A.5	Public liability and contract works insurance	item	1		£0.00
A.6	Scaffolding — independent access for ICF erection	wk	10		£0.00
A.7	Plant hire — telehandler / forklift for offload & ICF moves	wk	10		£0.00
A.8	Plant hire — small tools, generators, power & lighting	wk	10		£0.00
A.9	Hoarding / site enclosure / security	wk	10		£0.00
A.10	Temporary services — water, power, lighting (hire)	wk	10		£0.00
A.11	Site clean, waste management & skip rotation	wk	10		£0.00
A.12	Setting out and surveying — engineer's level checks	wk	10		£0.00
A.13	Site take-down, hand-over & demobilisation	item	1		£0.00
A.14	Pre-completion sound test (Approved Document E)	test			£0.00
A.15	Air-tightness test (Approved Document L)	test			£0.00
A.16	Day works allowance	sum			£0.00
	A — PRELIMINARIES SUBTOTAL				**£0.00**

B · ICF KIT SUPPLY

ICF material supply values are pre-priced from the associated Tremco CPG quotation. Pre-cut service fees are taken from each BuildEase take-off.

Ref	Description	Unit	Qty	Rate (£)	Total (£)
B.1 — ICF Block, Forms & Accessories					
B.1	ICF Materials — Bromfelde Corner (1 plot(s), 709 forms)	group	1	£40,821.58	£40,821.58
B.2 — BuildEase Pre-Cut Service Fee					
B.2	Pre-Cut Service — Bromfelde Corner	group	1	£3,942.16	£3,942.16
B.3 — Haulage					
B.3	Haulage to site — 4 loads: 4 x artic @ 200.0 mi (proposal delivery schedule: FB + L1, then L2, then L3 + L4)	item	1	£2,379.32	£2,379.32
B.4 — Alignment System					
B.4	Alignment System Rental — Bromfelde Corner (61 systems)	group	1	£3,200.00	£3,200.00
	B — ICF KIT SUPPLY SUBTOTAL				**£50,343.06**

C · CONCRETE SUPPLY, PUMP & PLACEMENT

Volumes are geometric void calculations (block length × course height × core thickness). Allow ~3% for plastic web displacement and ~5% wastage when ordering. Rates to be inserted by the contractor.

Ref	Description	Unit	Qty	Rate (£)	Total (£)
C.1 — Ready-Mix Concrete Supply (C28/35 typical to BS 8500)					
C.1	Ready-mix concrete — Bromfelde Corner (1 plot(s), geometric void)	m³	111.43		£0.00
C.2 — Concrete Pump Hire					
C.2	Boom pump hire — Bromfelde Corner	day	5		£0.00
C.2	Pump mobilisation / demobilisation	item	1		£0.00
C.3 — Concrete Vibration & Placement Plant					
C.3	Internal poker vibrator hire — site duration	wk	10		£0.00
C.3	Concrete banksman / poker operator	day			£0.00
	C — CONCRETE SUBTOTAL				**£0.00**

D · LABOUR — ICF INSTALL, FLOORS & ROOFS

ICF install days scaled proportionately against the Maycroft reference (52.65 forms per gang-day). Rates below are per 4-man gang per day. Floor and roof allowances are taken per group from the project configuration.

Ref	Description	Unit	Qty	Rate (£)	Total (£)
D.1 — ICF Install Gang					
D.1	ICF install — Bromfelde Corner (709 forms ÷ 52.65 forms/day = 13.5 gang-days)	gang-day	13.50		£0.00
D.1	Snag, pour & cure attendance (30% allowance, project total)	gang-day	4.00		£0.00
D.2 — Floor Structure (GF / 1F / 2F / 3F precast beam & block floors BY OTHERS - a 1-day slot at the end of each 2-week floor; joinery crew at					
D.2	Floor structure — Bromfelde Corner (4 floors × 1 gang-days)	gang-day	4		£0.00
D.3 — Roof Structure Labour (cut roofs C24 @ 600: main hipped roof with a gable to the NE party wall + hipped wing roof; natural slate 33 de					
D.3	Roof structure — Bromfelde Corner	gang-day	1		£0.00
	D — LABOUR SUBTOTAL				**£0.00**

F · REFERENCE DATA (informative only)

Per-group quantities calculated from the BuildEase take-off models. Values feed into Sections C and D. Render is excluded from this BOQ.

Group	Plots	Forms	Concrete (m³)	ICF install days	Floor + Roof days	Pre-cut (£)
Bromfelde Corner	1	709	111.43	13.50	5	£3,942.16
SITE	**1**	**709**	**111.43**	**13.50**	**5**	**£3,942.16**

PER-LIFT FORM BREAKDOWN

Group	Lift	4" Std	6" XR35 str	6" XR35 cnr	10" Std	Lift total
Bromfelde Corner	FB	0	60	20	0	80
Bromfelde Corner	L1	0	148	60	0	208
Bromfelde Corner	L2	0	161	48	0	209
Bromfelde Corner	L3	0	129	24	0	153
Bromfelde Corner	L4	0	51	8	0	59

GEOMETRIC CONSTANTS & CALCULATION BASIS

Block length	2.438 m	*96 inches*
Course height	0.4574 m	*18 inches*
4" Std straight volume	0.1133 m³	*Volume = length × course × core*
6" XR35 straight volume	0.1699 m³	*Volume = length × course × core*
10" Std straight volume	0.2832 m³	*Volume = length × course × core*
4" Std corner volume	0.0511 m³	*L-void; long 31.625" / short 15.625"*

6" XR35 corner volume	0.1133 m³	*L-void; long 43" / short 27"*
Maycroft install rate	52.65 forms/day	*Reference: 1053 forms ÷ 20 days*

Bill of Quantities Package - Finishes & Ancillary Trades

ES26-087 | Bromfelde Corner, 25 Bromfelde Road, Clapham | JAUS (via Tremco CPG UK)

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the Basis Point Design planning drawings P01-P16 Rev E (10.03.2022, 1:100 @ A3: plans, elevations, sections); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F) / L4 (3F) and the Roof; the Site total is their sum. Rates and amounts are by others.

Project	Bromfelde Corner, 25 Bromfelde Road, Clapham
Site	25 Bromfelde Road / Union Road corner, London SW4 6PP
Client	JAUS (via Tremco CPG UK)
Architect	Basis Point Design (planning drawings P01-P16 Rev E, 10.03.2022 - plans / elevations / sections, 1:100 @ A3)
Quotation ref	ES26-087
Document	Bill of Quantities Package - Finishes & Ancillary Trades
Date	02/11/2026
Scope	One corner building of 6 flats (GF Flats 1 / 2, 1F Flats 3 / 4, 2F Flats 5 / 6, 3F Flat 5 attic): 6in XR35 ICF external walls + 6in Standard separating walls on an FB foundation, three bays + the stair-core bay (as drawn, mitred) at GF / 1F, a 2-storey wing; precast B&B floors, steels and the 1F roof terrace by others; cut roofs (main hipped with a gable to the NE party wall, hipped wing), natural slate; gault brick slips with reconstituted stone detailing; heritage sash-style windows
Building height	**ENGLAND: the design must satisfy the Building Regulations 2010 (Approved Documents A-S) - building control by LABC / an approved inspector; NOT the Scottish technical handbooks. Building height (ADB Diagram D6, to the floor of the top storey): the 3F (Flat 5 attic) FFL is 8,229.6 above the GF FFL, ~8.38 m above the lowest adjoining ground (ground ASSUMED ~150 below GF FFL all round - to be confirmed on a measured survey) - BELOW 11 m (margin ~2.6 m), so the 11-18 m fire band (ADB B4 external-wall materials, sprinklers in new blocks of flats) does not apply. 4 storeys incl. the attic: the LABC Warranty technical manual caps ICF at 3 storeys unless an independent engineer inspects each pour (pre-pour) and signs off - the warranty provider must confirm. Flats = Consequence Class 2A (Approved Document A): floor-to-wall ties / anchorage are engineer-designed (outside the manufacturer tables).**
Engineer / specialists	**ENGINEER / SPECIALISTS TO DESIGN: STRUCTURAL ENGINEER: the indicative steels S1 / T1 / T2 incl. the TRANSFER beams under the 1F north wall (T1) and the wing east wall (T2) over the GF Flat 2 living room; padstones / pocket bearings in the ICF core (form at the pour of the lift below); the B&B bearings on the ICF core; floor-to-wall ties (Consequence Class 2A); the main roof (unpropped hip heads, room-in-roof without ties - structural ridge / purlins); the strip footing; the NE party-wall foundation next to No. 27. NOT FOR CONSTRUCTION.**
Prepared by	BuildEase (Tremco CPG UK) - BuildEase Design Suite quotation model
Status	**FOR INFORMATION, COORDINATION AND PRICING BY OTHERS - rates blank; NOT part of the Nudura ICF price; NOT FOR CONSTRUCTION**

PACKAGE OVERVIEW - pricing by others (all amounts formula-linked to each bill's Package Summary)

Bill	Package	Code / NRM2	Supply £	Install £	Total £
Bill 1	External Wall Facing to the ICF (gault brick slips, reconstituted stone, rendered cornice - spec TBC)	EXT NRM2 14 / 15	£0.00	£0.00	£0.00
Bill 2	Internal Linings - Walls, Separating Walls, Ceilings (attic on the slope), Tape, Beads & Skim	DRY NRM2 28	£0.00	£0.00	£0.00
Bill 3	Internal Doors, Flat Entrance Doors & Ironmongery	JOI NRM2 24	£0.00	£0.00	£0.00
Bill 4	Joinery - Skirtings, Architraves, Window Boards, Stairs & Balustrades	JOI NRM2 22	£0.00	£0.00	£0.00
Bill 5	Timber Stud Partitions (TLSTF) - Framing, Openings, Head Restraint & Fixings	JOI NRM2 16	£0.00	£0.00	£0.00
Bill 6	Substructure, Precast B&B Floors, Roof Terrace & Steels (coordination)	GRW / FLR / STR NRM2 5 / 11 / 14 / 16	£0.00	£0.00	£0.00
Bill 7	Roofs - Cut Roof Structure, Natural Slate, Bay Roofs, Rainwater, Abutments & Insulation	RFS / RFC NRM2 16 / 18	£0.00	£0.00	£0.00
Bill 8	Glazing, External Doors, Common Entrance, Balconies & Guarding	WIN / MET NRM2 25	£0.00	£0.00	£0.00
	GRAND TOTAL - finishes / ancillary trades, net (excl. VAT)		**£0.00**	**£0.00**	**£0.00**

Optional additions (enter %; blank = 0)		**%**		**Amount £**
Preliminaries	on the finishes net grand total			£0.00
Overheads & profit	on net total + preliminaries			£0.00
Contingency	on net total + preliminaries + OH&P			£0.00
	GRAND TOTAL finishes incl. preliminaries, OH&P and contingency (excl. VAT)			**£0.00**

ICF PACKAGE HOOK - BuildEase BOQ Builder (ICF kit, concrete, labour, preliminaries, programme)

Nudura ICF package (BuildEase BOQ Builder sheets of this workbook: Summary NET TOTAL)	**£50,343.06**
COMBINED TOTAL - finishes package (incl. additions) + ICF package, excl. VAT	**£50,343.06**

Pale-yellow cells are the only inputs (rates on each bill sheet, percentages and the ICF hook here). Everything else is a locked formula (protection has no password). Schedules A to D are reference only and are not priced. Named cells: FINISHES_NET_TOTAL, FINISHES_GRAND_TOTAL, ICF_PACKAGE_TOTAL, COMBINED_TOTAL.

IMPORTANT - This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the Basis Point Design planning drawings P01-P16 Rev E (10.03.2022, 1:100 @ A3: plans, elevations, sections); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F) / L4 (3F) and the Roof; the Site total is their sum. Rates and amounts are by others.

KEY QUANTITIES (site totals: one building, levels FB / L1-L4 + roof, net; linked to the bills)		
Gault brick-slip facing to the ICF	**38.84**	m2
Reconstituted stone window cills	**0.00**	m
Wall linings (ICF faces, separating walls, partitions, reveals)	**56.64**	m2
Ceilings (GF / 1F / 2F + attic on the slope)	**131.11**	m2
Skim coat	**187.76**	m2
Internal + flat entrance doorsets	**0.00**	nr
Skirting	**47.94**	m
Timber stud partitions (gross area)	**0.00**	m2
Partition door openings formed	**0.00**	nr
Precast B&B floors GF / 1F / 2F / 3F (by others)	**117.09**	m2
Natural slate on the slope (main + wing)	**0.00**	m2
Bay roofs (slope)	**0.00**	m2
Windows	**0.00**	nr
External / terrace / balcony doors (fit)	**0.00**	nr

Document control

Issue	Description	Date	By / Status
-	Quotation issue: finishes / ancillary-trades BOQ package for the Nudura ICF quotation (per level FB / L1-L4 + roof for one building of 6 flats), merged with the BuildEase BOQ Builder ICF bill + programme. Live pricing workbook: rates blank for pricing by others; ICF_PACKAGE_TOTAL linked to the BOQ Builder NET TOTAL	02/11/2026	BuildEase - T. Smith / For information / pricing by others - NOT FOR CONSTRUCTION

Contents

Finishes Cover (this sheet) - overview
General Notes
Summary of Bills (section breakdown)
Finishes Bill 1 External Facing
Finishes Bill 2 Internal Lining
Finishes Bill 3 Doors
Finishes Bill 4 Joinery
Finishes Bill 5 Partitions
Finishes Bill 6 Substructure Fl
Finishes Bill 7 Roof
Finishes Bill 8 Glazing
Schedule A Areas (not priced)
Schedule B Openings (not priced)
Schedule C Per Level (not priced)
Schedule D Partitions (not priced)

General Notes, Measurement Basis, Assumptions & Exclusions

ES26-087 | Bromfelde Corner, 25 Bromfelde Road, Clapham | JAUS (via Tremco CPG UK)

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the Basis Point Design planning drawings P01-P16 Rev E (10.03.2022, 1:100 @ A3: plans, elevations, sections); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F) / L4 (3F) and the Roof; the Site total is their sum. Rates and amounts are by others.

1 Purpose, status, England and building height

ENGLAND: the design must satisfy the Building Regulations 2010 (Approved Documents A-S) - building control by LABC / an approved inspector; NOT the Scottish technical handbooks. Building height (ADB Diagram D6, to the floor of the top storey): the 3F (Flat 5 attic) FFL is 8,229.6 above the GF FFL, ~8.38 m above the lowest adjoining ground (ground ASSUMED ~150 below GF FFL all round - to be confirmed on a measured survey) - BELOW 11 m (margin ~2.6 m), so the 11-18 m fire band (ADB B4 external-wall materials, sprinklers in new blocks of flats) does not apply. 4 storeys incl. the attic: the LABC Warranty technical manual caps ICF at 3 storeys unless an independent engineer inspects each pour (pre-pour) and signs off - the warranty provider must confirm. Flats = Consequence Class 2A (Approved Document A): floor-to-wall ties / anchorage are engineer-designed (outside the manufacturer tables).

1.1 ENGINEER / SPECIALISTS TO DESIGN (floors, steels, roof timbers, partitions and glazing are in the model for coordination only): STRUCTURAL ENGINEER: the indicative steels S1 / T1 / T2 incl. the TRANSFER beams under the 1F north wall (T1) and the wing east wall (T2) over the GF Flat 2 living room; padstones / pocket bearings in the ICF core (form at the pour of the lift below); the B&B bearings on the ICF core; floor-to-wall ties (Consequence Class 2A); the main roof (unpropped hip heads, room-in-roof without ties - structural ridge / purlins); the strip footing; the NE party-wall foundation next to No. 27.

1.2 This package presents the finishes and ancillary-trade quantities measured by BuildEase alongside the Nudura ICF quotation for Bromfelde Corner, 25 Bromfelde Road, Clapham (ref ES26-087). It is set out as a Bill of Quantities so that the client, their quantity surveyor and trade contractors can price and coordinate the works.

1.3 Status: FOR INFORMATION, COORDINATION AND PRICING BY OTHERS - NOT FOR CONSTRUCTION. Supply and install rates are left blank deliberately - BuildEase / Tremco CPG are not pricing these trades. The Excel workbook is a live pricing document: enter rates and every amount, subtotal and total updates by formula.

1.4 The ICF kit, concrete core, pumping, ICF / floor / roof labour and the build programme are in the BuildEase BOQ Builder sheets of this workbook (Cover / Programme / Summary / A-F). The finishes cover carries a named hook (ICF_PACKAGE_TOTAL) linked to that NET TOTAL.

1.5 PROGRAMME (BOQ Builder sheet 'Programme', 1 ICF crew of 8 + 1 joinery crew of 3): 2 WEEKS PER FLOOR - FB, GF, 1F, 2F and 3F each one 2-week block (ICF erection + snag 6 days, pour 1, cure 2, floor slot 1; the roof after the 3F pour): 50 working days = 10 weeks. Sequence: ICF FB d0-6; pour d6-7; cure d7-9; GF precast beam & block floor d9-10; ICF L1 d10-16; pour d16-17; cure d17-19; 1F B&B floor d19-20; ICF L2 d20-26; pour d26-27; cure d27-29; 2F B&B floor d29-30; ICF L3 d30-36; pour d36-37; cure d37-39; 3F B&B floor d39-40; ICF L4 d40-46; pour d46-47; cure d47-49; roof d49-50. ICF concrete 111.43 m3 (geometric, 709 ordered forms: FB 12.46 / L1 31.95 / L2 32.80 / L3 24.64 / L4 9.57) in 5 pump days. ALIGNMENT: the proposal prices 4 stillages x 10 weeks hire (GBP 3,200.00); on this programme the alignment is needed from the first ICF lift (FB, day 0) to the last pour (L4, day 47) = 10 weeks on hire - the same as priced. The proposal prices the alignment hire for this programme.

1.6 **This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price.**

1.7 **Quantities are measured from the BuildEase quotation model of the Basis Point Design planning drawings P01-P16 Rev E (10.03.2022, 1:100 @ A3: plans, elevations, sections); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F) / L4 (3F) and the Roof; the Site total is their sum. Rates and amounts are by others.**

1.8

2 Basis of measurement

Measured generally in accordance with the principles of NRM2 (RICS New Rules of Measurement): work measured net as fixed in position, grouped by work section, units m / m2 / nr / item. NRM2 is referenced for structure only; descriptions are BuildEase's own.

2.1 Quantities are NET. No allowance for waste, laps, cutting or breakage is included unless stated; an "Order guide" with a stated waste % is guidance only.

2.2 Quantity columns: one column PER MODEL LEVEL - FB foundation, L1 GF, L2 1F (incl. the 2-storey wing and the bays), L3 2F, L4 3F (Flat 5 attic: eaves walls + NE party wall) - and a ROOF column. One building: the Site total is the sum of the columns (multiplier 1) and is a live formula.

2.3 Sources: Basis Point Design planning drawings P01-P16 Rev E (10.03.2022, 1:100 @ A3: GF / 1F / 2F / 3F plans, elevations P13 / P14, sections); the BuildEase quotation model 03_Models/BC_build.skp through its spec (04_Logs/specs/BC_spec.json, BC_floors.json), build reports (04_Logs/build/BC: bcw_fit, roof_* / struct_*, eaves, BCP_* TLSTF partitions) and the Report Tool component export (04_Logs/takeoff/BC_components.json: inner / outer EPS face areas of the 1181 modelled forms, openings net). Measured offline by 05_Scripts/bc_boq.py (no live model).

2.4

3 Assumptions

Walls: external 6in XR35 (355.6 overall), separating walls (stair core + flat separating wall) 6in Standard (285.8). The ICF external face is on the drawn outer face (drawn 220 brick: rooms lose ~136). Frames tight to the back of the outer EPS (101.8): internal reveal 211.

3.1 Levels: FB -914.4 to 0 (2 courses on a strip footing by others, top = GF FFL); FFLs GF 0 / 1F 2,743.2 / 2F 5,486.4 / 3F 8,229.6; 3F eaves walls cut at 9,144 (+ 150 plate = 9,294); NE party wall to 11,430 (under the covering); ridge ~12.00 m above GF FFL (geometric estimate: 33 deg planes over the plate line, heel ignored).

3.2

External finishes: gault brick slips with reconstituted stone detailing, rendered cornice, natural slate (materials table P13 / P14); ground ~150 below GF FFL all round (not surveyed). The NE party wall face against No. 27 has no facing where it abuts.

3.3

Floors: precast B&B BY OTHERS (GF 150 + 150 insulation + 50 screed; 1F-3F 150 + 100 topping + 25 screed) per BC_floors.json; ceilings under them; the stair core a triple-volume void with its ceiling at the 3F soffit; the Flat 5 attic vaulted on the slope (ASSUMED).

3.4

Internal doors: 18 doorsets / 18 leaves - TLSTF partition doors + 6 PROVISIONAL FD30S flat entrance doors; leaves = the largest standard 1,981 leaf that fits the opening less 68, pairs at 1,150 and over. Partitions: TLSTF 38 x 89 C16 - GF 16 walls 33.4 m / 1F 15 walls 33.0 m / 2F 9 walls 17.7 m = 84.1 m, 12 door openings.

3.5

Roofs: 33 deg cut roofs, member counts from struct_Main / struct_Wing; rafter length estimated from the slope area (194.5 m2) at 600 c/c; hips / ridges / valley from the straight-skeleton height field; no rooflights / PV (none drawn); 4 bay roofs provisional.

3.6

4 Exclusions (not measured in this package)

Nudura ICF formwork and accessories (in the Nudura price). ICF wall concrete, pumping, ICF / floor / roof labour and preliminaries are in the BOQ Builder sheets.

4.1

Supply of windows, doors and the common entrance are listed for pricing by the window / door suppliers (Bill 8) - not by BuildEase. External works, drainage, landscaping, cycle / refuse stores, boundary walls, gates and railings (shown on the planning drawings), the gardens.

4.2

Floor finishes, decorations, kitchens, sanitaryware, M&E services (heating, MVHR, electrics, door entry) and builder's work.

4.3

4.4 Fire-stopping and fire-rated service penetrations, sealants and mastics, except where expressly described.

5 Open items / to be confirmed

STRUCTURAL ENGINEER: the indicative steels S1 / T1 / T2 incl. the TRANSFER beams under the 1F north wall (T1) and the wing east wall (T2) over the GF Flat 2 living room; padstones / pocket bearings in the ICF core (form at the pour of the lift below); the B&B bearings on the ICF core; floor-to-wall ties (Consequence Class 2A); the main roof (unpropped hip heads, room-in-roof without ties - structural ridge / purlins); the strip footing; the NE party-wall foundation next to No. 27.

5.1

BEAM SUPPLIER: GF / 1F / 2F / 3F precast B&B layouts (Bill 6), the Flat 5 stair opening trimming and the vents / sleeves through the FB (form BEFORE the FB pour).

5.2

ARCHITECT / BUILDING CONTROL (England, Approved Documents): flat entrance doors (NOT in the model - 6 openings in the ICF separating walls to be added, RFI); ADB vol 1 (FD30S entrance doors, protected entrance halls for Flats 5 / 6, Flat 5 multi-storey flat); Part E (ICF separating walls and B&B separating floors - not Robust Details: pre-completion testing); Part K (all window sills 457 - guarding / restrictors at 1F+); Part M (Flat 1 "disabled adapted", M4(3)); Parts L / O / F (acoustic windows, overheating in London).

5.3

LABC WARRANTY: 4 storeys incl. the attic - ICF capped at 3 storeys unless an independent engineer inspects pre-pour and signs off; provider to confirm.

5.4

PARTY WALL: the NE wall abuts No. 27 Bromfelde Road - Party Wall etc. Act 1996 notices, the junction with No. 27's roof / facing, fire-stopping at the compartment-wall head (Bills 1A.9, 6A.6, 7B.10).

5.5

SITE ACCESS: corner plot on residential streets in Clapham - artic access / unloading / parking suspensions by the contractor.

5.6

Assumed (not drawn / not modelled): ground ~150 below GF FFL all round; brick-SLIP facing on the ICF (not a brick outer leaf); the Flat 5 attic vaulted on the slope; a warm main roof / cold wing roof; the wing plate level; bay roofs at 33 deg; 1 privacy set + 1 FD30S entrance door per flat; downpipes ~1 per 10 m of gutter; the stairs (not modelled).

5.7

DATA CHECK: partition door opening 554 is below the smallest standard doorset (533 + 68) - cupboard / store door? check

5.8

6 What IS in the Nudura price (Quotation ES26-087, NET GBP 50,343.06)

Nudura ICF kit as modelled in the BuildEase Design Suite: 1181 forms modelled (FB 117 / L1 388 / L2 372 / L3 227 / L4 77) / 709 to order after the cut optimiser (FB 80 / L1 208 / L2 209 / L3 153 / L4 59), 6in XR35 external walls + 6in Standard separating walls, materials GBP 40,821.58.

6.1

6.2 Accessories: VJC clips, end caps, Form-Lock, lintel closures, spray foam.

BuildEase Pre-Cut Service GBP 3,942.16; alignment system 4 stillages x 10 weeks hire GBP 3,200.00; haulage 4 loads: 4 x artic @ 200.0 mi GBP 2,379.32 (3 deliveries: FB + L1, then L2, then L3 + L4; 33 pallets).

6.3

6.4 Nothing in Bills 1 to 8 of this finishes package is included in the Nudura price.

7 Pricing instructions to tenderers

Each bill item has a SUPPLY rate and an INSTALL rate. Insert rates only in the pale-yellow cells of the Excel workbook: Supply = Site total qty x Supply rate; Install = Site total qty x Install rate; Line total = Supply + Install. Items measured as "item" are lump sums: the rate entered is the amount.

7.1

Each bill ends with a Package Summary (section subtotals for Supply / Install / Total and the package total). The Cover carries the full overview: one row per bill, grand totals, optional Preliminaries, Overheads & profit and Contingency percentages (pale-yellow cells; blank = 0) and the ICF package hook.

7.2

All other cells are locked by sheet protection (no password - Review > Unprotect Sheet if a change is genuinely needed) so formulas cannot be overwritten by accident.

7.3

Re-measure and verify all quantities before pricing or ordering. State any qualification against the item in the Notes column.

7.4

The Order guide figures and Schedules A to D are not measured bill items and must not be priced as such. All amounts exclude VAT.

7.5

Summary of Bills - section breakdown

ES26-087 | Bromfelde Corner, 25 Bromfelde Road, Clapham | JAUS (via Tremco CPG UK) - amounts by others, excl. VAT

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the Basis Point Design planning drawings P01-P16 Rev E (10.03.2022, 1:100 @ A3: plans, elevations, sections); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F) / L4 (3F) and the Roof; the Site total is their sum. Rates and amounts are by others.

Bill	Section	Description	Supply £	Install £	Total £
1	1A	Facing to the ICF - gault brick slips (NRM2 14 / 15 - package EXT; system by others, SPEC TBC)	£0.00	£0.00	£0.00
1	1B	Reconstituted stone detailing and rendered cornice (NRM2 14 / 15 - package EXT; stone supplier, SPEC TBC)	£0.00	£0.00	£0.00
1	1C	Coordination items (supply by others)	£0.00	£0.00	£0.00
Bill 1 - External Wall Facing to the ICF (gault brick slips, reconstituted stone, render			**£0.00**	**£0.00**	**£0.00**
2	2A	Wall linings (NRM2 28 / package DRY)	£0.00	£0.00	£0.00
2	2B	Ceilings (NRM2 28 / package DRY)	£0.00	£0.00	£0.00
2	2C	Jointing, beads and skim (NRM2 28 / package DRY)	£0.00	£0.00	£0.00
Bill 2 - Internal Linings - Walls, Separating Walls, Ceilings (attic on the slope), Tape,			**£0.00**	**£0.00**	**£0.00**
3	3A	Internal doorsets (NRM2 24 / package JOI)	£0.00	£0.00	£0.00
3	3B	Ironmongery (NRM2 24 / package JOI)	£0.00	£0.00	£0.00
Bill 3 - Internal Doors, Flat Entrance Doors & Ironmongery (package JOI)			**£0.00**	**£0.00**	**£0.00**
4	4A	Skirtings (NRM2 22 / package JOI)	£0.00	£0.00	£0.00
4	4B	Architraves (NRM2 22 / package JOI)	£0.00	£0.00	£0.00
4	4C	Window boards (NRM2 22 / package JOI)	£0.00	£0.00	£0.00
4	4D	Stairs, balustrades and sundry joinery (NRM2 22 / package JOI) - INDICATIVE, not modelled	£0.00	£0.00	£0.00
Bill 4 - Joinery - Skirtings, Architraves, Window Boards, Stairs & Balustrades (package			**£0.00**	**£0.00**	**£0.00**
5	5A	Timber stud partitions, non-loadbearing - framing (NRM2 16 / package JOI)	£0.00	£0.00	£0.00
5	5B	Partition timber - supply (NRM2 16 / package JOI)	£0.00	£0.00	£0.00
5	5C	Forming door openings in partitions (NRM2 16 / package JOI)	£0.00	£0.00	£0.00
5	5D	Head restraint, acoustic and fixings (NRM2 16 / package JOI)	£0.00	£0.00	£0.00
Bill 5 - Timber Stud Partitions (TLSTF) - Framing, Openings, Head Restraint & Fixings			**£0.00**	**£0.00**	**£0.00**
6	6A	Substructure (NRM2 5 / 11 - package GRW; by others - engineer; coordination quantities)	£0.00	£0.00	£0.00
6	6B	GF floor (FFL 0.0) - precast beam & block BY OTHERS (NRM2 14 / 16 - package FLR; beam supplier design)	£0.00	£0.00	£0.00
6	6C	1F floor (FFL 2,743.2) - precast beam & block BY OTHERS (NRM2 14 / 16 - package FLR; beam supplier design)	£0.00	£0.00	£0.00
6	6D	2F floor (FFL 5,486.4) - precast beam & block BY OTHERS (NRM2 14 / 16 - package FLR; beam supplier design)	£0.00	£0.00	£0.00
6	6E	3F floor (FFL 8,229.6) - precast beam & block BY OTHERS (NRM2 14 / 16 - package FLR; beam supplier design)	£0.00	£0.00	£0.00
6	6F	Steels (NRM2 14 - package STR; ENGINEER - INDICATIVE, sections not designed)	£0.00	£0.00	£0.00
Bill 6 - Substructure, Precast B&B Floors, Roof Terrace & Steels (coordination) (pack			**£0.00**	**£0.00**	**£0.00**
7	7A	Roof structure - cut roofs C24 @ 600 (NRM2 16 - package RFS; roof designer / engineer)	£0.00	£0.00	£0.00
7	7B	Roof coverings, eaves, rainwater and abutments (NRM2 18 / 33 - package RFC)	£0.00	£0.00	£0.00
7	7C	Roof insulation and VCL (NRM2 18 / 28 - package RFC)	£0.00	£0.00	£0.00
Bill 7 - Roofs - Cut Roof Structure, Natural Slate, Bay Roofs, Rainwater, Abutments & I			**£0.00**	**£0.00**	**£0.00**
8	8A	Windows - white heritage sash-style double-glazed, acoustic, openable (NRM2 25 - package WIN; window supplier)	£0.00	£0.00	£0.00
8	8B	External doors, terrace / balcony doors and the common entrance (NRM2 25 - package WIN)	£0.00	£0.00	£0.00
8	8C	Balconies, Juliet balconies and the terrace doors (NRM2 25 / 22 - package MET)	£0.00	£0.00	£0.00
8	8D	Items not modelled (PROVISIONAL)	£0.00	£0.00	£0.00
Bill 8 - Glazing, External Doors, Common Entrance, Balconies & Guarding (package WI			**£0.00**	**£0.00**	**£0.00**
TOTAL - finishes / ancillary trades, net (agrees with the Cover overview)			**£0.00**	**£0.00**	**£0.00**

Schedules A to D are reference schedules and are not priced. Preliminaries, overheads & profit, contingency and the ICF package (BuildEase BOQ Builder) are applied on the Cover.

Bill 1 - External Wall Facing to the ICF (gault brick slips, reconstituted stone, rendered cornice - spec TBC)

Gault brick-slip facing to the ICF EPS faces, plinth, corners, reveals, the reconstituted stone detailing and the eaves cornice (systems by others, spec TBC). [NRM2 14 / 15 / package EXT]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the Basis Point Design planning drawings P01-P16 Rev E (10.03.2022, 1:100 @ A3: plans, elevations, sections); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F) / L4 (3F) and the Roof; the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB foundation	L1 GF	L2 1F	L3 2F	L4 3F attic	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	1	6						Levels: FB = foundation: 2 courses (XR35 envelope + Std separating walls), -914 to 0 on the strip footing (by others); L1 = ground floor, Flats 1 / 2: 6 courses 0-2,743 (ceiling at the 1F B&B soffit 2,468); L2 = first floor, Flats 3 / 4 + the bays + the 2-storey wing: 6 courses 2,743-5,486 (soffit 5,211); L3 = second floor, Flats 5 / 6: 6 courses 5,486-8,230 (soffit 7,955); L4 = 3F Flat 5 attic: eaves walls cut at
1A	**Facing to the ICF - gault brick slips (NRM2 14 / 15 - package EXT; system by others, SPEC TBC)**														
	Basis Point Design elevations P13 / P14 (materials table): external walls GAULT BRICK with RECONSTITUTED STONE detailing, rendered (plaster-moulded) eaves cornice, natural slate roof. The ICF external face is set on the drawn outer face (drawn 220 brick wall), so the facing is measured as a gault BRICK-SLIP system on the ICF EPS (adhesive / mechanically fixed on a carrier, spec TBC) - a full 102 brick outer leaf would sit OUTSIDE the planning line (architect). Areas are the modelled ICF outer EPS faces (Report Tool component export, openings net), per storey; the NE party wall face against No. 27 Bromfelde Road is measured separately (1A.9). Ground ASSUMED ~150 below GF FFL all round - a 150 plinth band on the FB is measured. Brick areas are NOT reduced for the stone details (1B).														
1A.1	Gault brick-slip facing system to the ICF EPS face (slips, adhesive / carrier, pointing - spec TBC, by others), GF to the 3F eaves walls, net of openings; excludes the NE party wall face	m2		126.45	133.16	96.00	38.84		**394.45**			£0.00	£0.00	**£0.00**	Order guide +10% = 433.9
1A.2	Plinth to the exposed FB face, ground (~-150) to GF FFL / DPC (engineering-brick slips or dark plinth render on the EPS - spec TBC)	m2	8.48						**8.48**			£0.00	£0.00	**£0.00**	Envelope perimeter 62.9 m less the NE party wall x 150 band
1A.3	Brick-slip corner pieces (L-shaped / pistol slips) to the external 90 deg corners, per storey	m		19.20	16.46	10.97	3.66		**50.29**			£0.00	£0.00	**£0.00**	Order guide +10% = 55.3; L1 7 nr, L2 6 nr, L3 4 nr, L4 4 nr
1A.4	Brick-slip corner pieces cut / special angle to the mitred bay corners (127 / 143 deg external), GF + 1F	m		24.69	24.69	2.74	0.91		**53.04**			£0.00	£0.00	**£0.00**	Order guide +10% = 58.3; L1 9 nr, L2 9 nr, L3 1 nr, L4 1 nr
1A.5	Reveal returns at windows / doors in the ICF (head + jambs; frames tight to the back of the outer EPS): slips, girth 102 + facing zone, incl. stop beads	m2		10.51	9.53	7.53			**27.57**			£0.00	£0.00	**£0.00**	Order guide +10% = 30.3; sills = stone cills (1B.1)
1A.6	Base / starter track, DPC and insect mesh at the GF DPC line (facing start), incl. termination of the plinth	m		50.02					**50.02**			£0.00	£0.00	**£0.00**	Order guide +10% = 55.0; NE party wall + GF door thresholds deducted (4.5 m)
1A.7	Movement / sealant joint between the facing / reveal returns and the window and door frames (backer rod + low-modulus sealant)	m		103.21	93.64	73.93			**270.78**			£0.00	£0.00	**£0.00**	Order guide +10% = 297.9
1A.8	Movement joints in the slip system (vertical / horizontal per the system manufacturer, incl. at each floor line and the bays)	item										£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Allowance - system manufacturer
1A.9	NE party wall face against No. 27 Bromfelde Road: NO facing ASSUMED where it abuts No. 27; weathering (render / slips) only where exposed above the neighbour's roof - PROVISIONAL, party wall surveyor / architect	m2		21.96	22.22	21.88	20.26		**86.32**			£0.00	£0.00	**£0.00**	ICF outer faces of the NE wall (component export); exposed area TBC on a survey of No. 27
1B	**Reconstituted stone detailing and rendered cornice (NRM2 14 / 15 - package EXT; stone supplier, SPEC TBC)**														
	Read off the elevations (heritage street look): stone cills to every window, head mouldings over the windows / doors, bay entablatures and cill bands with corbels at the GF / 1F bays, a rendered (plaster-mould) eaves cornice with brackets to the main eaves and the wing, and the stair-core entrance surround. Numbers from the spec openings; lengths from the model outline. Fixing into the ICF (webs / resin anchors, cramps) by the stone supplier - INDICATIVE, profiles by the architect.														
1B.1	Reconstituted stone window cills, weathered + throated, 75 horns each end, bedded on the ICF / DPC tray	m		13.74	14.13	13.16			**41.03**			£0.00	£0.00	**£0.00**	L1 19 nr, L2 18 nr, L3 16 nr
1B.2	Reconstituted stone head moulding / lintel face over each window and door (profile as the elevations)	nr		23.00	21.00	18.00			**62.00**			£0.00	£0.00	**£0.00**	One per opening in the ICF (spec)
1B.3	Bay entablature / cornice at the bay heads (1F head, under the bay roofs) - 4 bays	m			16.67				**16.67**			£0.00	£0.00	**£0.00**	Bay outer faces (model outline: 1F outside the 2F line)
1B.4	Stone cill band with corbel blocks at the bay window cills (GF + 1F, as drawn) - PROVISIONAL	m		16.67	16.67				**33.34**			£0.00	£0.00	**£0.00**	Elevations P13
1B.5	Rendered / plaster-moulded eaves cornice with modillion brackets (or GRP / precast cornice to match - spec TBC) at the main eaves walls (3F) and the wing eaves (1F)	m			13.60		42.49		**56.09**			£0.00	£0.00	**£0.00**	Materials table: "Rendered cornice - plaster mould to preserve street look"
1B.6	Stair-core entrance: stone surround / hood to the double-height glazed entrance (Union Road, as drawn)	nr		1.00					**1.00**			£0.00	£0.00	**£0.00**	PROVISIONAL
1C	**Coordination items (supply by others)**														
1C.1	Door thresholds / weathering at the external and terrace / balcony doors (low thresholds, Part M) - by the door supplier	nr		4.00	3.00	2.00			**9.00**			£0.00	£0.00	**£0.00**	Coordination only
1C.2	Head closure / ventilation trim of the facing under the eaves soffits and the bay roofs	m			30.27		42.49		**72.76**			£0.00	£0.00	**£0.00**	Order guide +10% = 80.0
1C.3	Wall-mounted rainwater pipes / brackets through the facing, fixings into the ICF webs (positions per the drainage design)	item										£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Bill 7B downpipes

Ref	Description	Unit	FB foundation	L1 GF	L2 1F	L3 2F	L4 3F attic	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	1	6						Levels: FB = foundation: 2 courses (XR35 envelope + Std separating walls), -914 to 0 on the strip footing (by others); L1 = ground floor, Flats 1 / 2: 6 courses 0-2,743 (ceiling at the 1F B&B soffit 2,468); L2 = first floor, Flats 3 / 4 + the bays + the 2-storey wing: 6 courses 2,743-5,486 (soffit 5,211); L3 = second floor, Flats 5 / 6: 6 courses 5,486-8,230 (soffit 7,955); L4 = 3F Flat 5 attic: eaves walls cut at

PACKAGE SUMMARY - Bill 1 External Wall Facing to the ICF (gault brick slips, reconstituted stone, rendered cornice - spec TBC) (package EXT; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
1A	Facing to the ICF - gault brick slips (NRM2 14 / 15 - package EXT; system by others, SPEC TBC)	£0.00	£0.00	**£0.00**
1B	Reconstituted stone detailing and rendered cornice (NRM2 14 / 15 - package EXT; stone supplier, SPEC TBC)	£0.00	£0.00	**£0.00**
1C	Coordination items (supply by others)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 1, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 2 - Internal Linings - Walls, Separating Walls, Ceilings (attic on the slope), Tape, Beads & Skim

Dry linings to the ICF inner faces (thermal barrier to the EPS), the separating walls (Part E), TLSTF partitions, reveals, the MF ceilings under the B&B floors and the attic room-in-roof. [NRM2 28 / package DRY]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the Basis Point Design planning drawings P01-P16 Rev E (10.03.2022, 1:100 @ A3: plans, elevations, sections); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F) / L4 (3F) and the Roof; the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB foundation	L1 GF	L2 1F	L3 2F	L4 3F attic	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	1	6						Levels: FB = foundation: 2 courses (XR35 envelope + Std separating walls), -914 to 0 on the strip footing (by others); L1 = ground floor, Flats 1 / 2: 6 courses 0-2,743 (ceiling at the 1F B&B soffit 2,468); L2 = first floor, Flats 3 / 4 + the bays + the 2-storey wing: 6 courses 2,743-5,486 (soffit 5,211); L3 = second floor, Flats 5 / 6: 6 courses 5,486-8,230 (soffit 7,955); L4 = 3F Flat 5 attic: eaves walls cut at
2A	**Wall linings (NRM2 28 / package DRY)**														
	Measured on the modelled ICF EPS faces (component export, openings net) by height zone: each storey from its FFL to the precast beam soffit of the floor above (GF 0-2,468, 1F 2,743-5,211, 2F 5,486-7,955); the 3F (Flat 5 attic) faces in full (eaves walls to 9,144, NE party wall). The B&B floor zones are not lined (the stair-core faces in the triple-volume stairwell at the floor zones are NOT measured - allow). The 6in Standard separating walls (stair core + flat separating wall) both faces. TLSTF partitions both faces, door gaps deducted (2,100 high). EPS faces must be covered by a thermal barrier (min. 12.5 mm board, mechanically fixed to the ICF webs) whatever the finish.														
2A.1	GF ICF external-wall inner faces: 12.5 mm wallboard on dabs + mechanical fixings to the ICF webs (MR board in the bathrooms / kitchens)	m2		112.72					**112.72**			£0.00	£0.00	**£0.00**	Order guide +10% = 124.0
2A.2	1F ICF external-wall inner faces (incl. the wing + bays): 12.5 mm wallboard on dabs + mechanical fixings (MR in wet rooms)	m2			122.21				**122.21**			£0.00	£0.00	**£0.00**	Order guide +10% = 134.4
2A.3	2F ICF external-wall inner faces: 12.5 mm wallboard on dabs + mechanical fixings (MR in wet rooms)	m2				96.62			**96.62**			£0.00	£0.00	**£0.00**	Order guide +10% = 106.3
2A.4	3F Flat 5 attic ICF inner faces (eaves walls + NE party wall to the roof): 12.5 mm board mechanically fixed - THERMAL BARRIER to the EPS	m2					56.64		**56.64**			£0.00	£0.00	**£0.00**	Order guide +10% = 62.3
2A.5	ICF separating walls (6in Standard: stair core + the flat separating wall) - both faces: lining to the acoustic design (Part E - ICF is not a Robust Detail: independent lining / dense board as the acoustician; pre-completion sound testing)	m2		65.62	58.61	55.41			**179.65**			£0.00	£0.00	**£0.00**	Order guide +10% = 197.6; L1 13.3 m, L2 11.9 m, L3 11.2 m
2A.6	TLSTF partitions - both faces: 12.5 mm board on 38 x 89 studs (MR in the bathrooms; acoustic board where Part E E2 requires)	m2		159.13	142.17	84.29			**385.59**			£0.00	£0.00	**£0.00**	Order guide +10% = 424.2
2A.7	Internal reveals to windows / doors in the ICF, jambs and heads, 211 deep: board / bonding + skim	m2		21.81	19.79	15.62			**57.22**			£0.00	£0.00	**£0.00**	Order guide +10% = 62.9
2B	**Ceilings (NRM2 28 / package DRY)**														
	Ceilings under the precast B&B floors = the floor-above outline (BC_floors.json) inside the ICF inner faces, less the separating-wall and partition footprints: the 1F floor includes the 12.57 m2 terrace (ceiling of GF Flat 2 under it); the stair core is a triple-volume void (no 1F / 2F floor) - its ceiling is the 3F floor soffit (~8.0 m, in 2B.3). 1F also has the rooms under the wing roof and the bay roofs (18.4 m2 on ceiling joists). The 3F Flat 5 attic is a room-in-roof: linings on the rafters ON THE SLOPE (plan 110.0 m2 x 1.192) - ASSUMED vaulted to the ridge (PROVISIONAL).														
2B.1	GF ceilings under the 1F B&B (separating floor): MF suspended ceiling + 2 x 15 dense board / acoustic hangers per Part E	m2		132.99					**132.99**			£0.00	£0.00	**£0.00**	Order guide +10% = 146.3
2B.2	1F ceilings under the 2F B&B (separating floor, MF ceiling as 2B.1) + the wing / bay rooms (12.5 board to the ceiling joists)	m2			116.73				**116.73**			£0.00	£0.00	**£0.00**	Order guide +10% = 128.4
2B.3	2F ceilings under the 3F B&B (MF ceiling; separating where over Flat 6) incl. the top of the stair core	m2				102.14			**102.14**			£0.00	£0.00	**£0.00**	Order guide +10% = 112.3
2B.4	Flat 5 attic (room-in-roof): 12.5 mm board (or insulated board) on the rafter soffits, measured on the 33 deg slope - PROVISIONAL	m2					131.11		**131.11**			£0.00	£0.00	**£0.00**	Order guide +10% = 144.2; confirm flat collar ceiling / eaves storage
2C	**Jointing, beads and skim (NRM2 28 / package DRY)**														
2C.1	Scrim tape, board joints (walls / 1.2 m; ceilings / 1.2 + 2.4 m)	m		465.64	431.56	337.62	211.09		**1,445.91**			£0.00	£0.00	**£0.00**	Order guide +10% = 1,590.5
2C.2	Scrim tape, internal angles wall to wall (4 per partition + 4 per separating-wall run + the reflex ICF corners)	m		230.43	216.71	123.44	0.91		**571.50**			£0.00	£0.00	**£0.00**	Estimate - no room model; Order guide +10% = 628.7
2C.3	Scrim tape, wall to ceiling angles (ICF inner perimeter + partition / separating-wall heads both sides)	m		153.38	151.71	105.80	47.94		**458.83**			£0.00	£0.00	**£0.00**	Estimate; Order guide +10% = 504.7
2C.4	Angle bead, window / door reveals	m		103.21	93.64	73.93			**270.78**			£0.00	£0.00	**£0.00**	Order guide +10% = 297.9
2C.5	Skim coat, 2-3 mm, to all net wall, reveal and ceiling board faces	m2		492.27	459.51	354.08	187.76		**1,493.61**			£0.00	£0.00	**£0.00**	Face layer only
2D	**Ordering guide (not a measured item)**														
2D.1	*Plasterboard to purchase, all types, before waste (MF ceilings at 2 layers)*	*m2*		*625.26*	*576.24*	*456.21*	*187.76*		*1,845.46*					*not priced*	*Guide only (+10% waste)*

PACKAGE SUMMARY - Bill 2 Internal Linings - Walls, Separating Walls, Ceilings (attic on the slope), Tape, Beads & Skim (package DRY; amounts by others, excl. VAT)

Ref	Description	Unit	FB foundation	L1 GF	L2 1F	L3 2F	L4 3F attic	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	1	6						Levels: FB = foundation: 2 courses (XR35 envelope + Std separating walls), -914 to 0 on the strip footing (by others); L1 = ground floor, Flats 1 / 2: 6 courses 0-2,743 (ceiling at the 1F B&B soffit 2,468); L2 = first floor, Flats 3 / 4 + the bays + the 2-storey wing: 6 courses 2,743-5,486 (soffit 5,211); L3 = second floor, Flats 5 / 6: 6 courses 5,486-8,230 (soffit 7,955); L4 = 3F Flat 5 attic: eaves walls cut at

Section	Description	Supply £	Install £	Total £
2A	Wall linings (NRM2 28 / package DRY)	£0.00	£0.00	**£0.00**
2B	Ceilings (NRM2 28 / package DRY)	£0.00	£0.00	**£0.00**
2C	Jointing, beads and skim (NRM2 28 / package DRY)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 2, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 3 - Internal Doors, Flat Entrance Doors & Ironmongery

Internal doorsets and ironmongery per level from the TLSTF partition doors + provisional FD30S flat entrance doors (18 doorsets, 18 leaves). [NRM2 24 / package JOI]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the Basis Point Design planning drawings P01-P16 Rev E (10.03.2022, 1:100 @ A3: plans, elevations, sections); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F) / L4 (3F) and the Roof; the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB foundation	L1 GF	L2 1F	L3 2F	L4 3F attic	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	1	6						Levels: FB = foundation: 2 courses (XR35 envelope + Std separating walls), -914 to 0 on the strip footing (by others); L1 = ground floor, Flats 1 / 2: 6 courses 0-2,743 (ceiling at the 1F B&B soffit 2,468); L2 = first floor, Flats 3 / 4 + the bays + the 2-storey wing: 6 courses 2,743-5,486 (soffit 5,211); L3 = second floor, Flats 5 / 6: 6 courses 5,486-8,230 (soffit 7,955); L4 = 3F Flat 5 attic: eaves walls cut at
3A	**Internal doorsets (NRM2 24 / package JOI)**														
	From the TLSTF door report (12 openings in the partitions, GF / 1F / 2F). Leaf = the largest standard 1,981 leaf that fits the opening less 68 (2 x 32 lining + clearances); openings of 1,150 and over get a PAIR. The 6 flat ENTRANCE doors off the common stair are NOT in the planning model / spec (no openings in the ICF separating walls) - measured PROVISIONALLY at one FD30S doorset per flat (926 leaf): the openings must be added to the ICF before the pour (RFI). ENGLAND: ADB vol 1 - flat entrance doors FD30S self-closing; Flats 5 / 6 (2F floor > 4.5 m above ground) need a protected entrance hall (FD20 doors) or an alternative; GF Flat 1 is drawn "disabled adapted" (M4(3) clear widths) - architect.														
3A.1	Internal doorset, 838 x 1,981 leaf, 32 x 115 lining set (119 partition), stops	nr		3.00	6.00	1.00			**10.00**			£0.00	£0.00	**£0.00**	GF-P07-D1 (926), GF-P10-D1 (926), GF-P13-D1 (926), 1F-P02-D1 (926), 1F-P03-D1 (926), 1F-P06-D1 (926), 1F-P07-D1 (926), 1F-P08-D1 (926), 1F-P12-D1 (926), 2F-P09-D1 (926)
3A.2	Internal doorset, 762 x 1,981 leaf, 32 x 115 lining set (119 partition), stops	nr			1.00				**1.00**			£0.00	£0.00	**£0.00**	1F-P12-D2 (842)
3A.3	Internal doorset, 533 x 1,981 leaf, 32 x 115 lining set (119 partition), stops	nr				1.00			**1.00**			£0.00	£0.00	**£0.00**	2F-P05-D1 (554)
3A.4	Flat entrance doorset FD30S, 926 x 1,981 leaf, self-closing, intumescent + smoke seals, lining to the 286 ICF separating wall, door viewer, multi-point lock - PROVISIONAL (not in the model)	nr		2.00	2.00	2.00			**6.00**			£0.00	£0.00	**£0.00**	1 per flat (Flats 1-6); positions RFI
3A.5	Upgrade of the doors onto the protected entrance halls of Flats 5 / 6 to FD20 self-closing IF the fire strategy requires (floor > 4.5 m, ADB vol 1 s.3) - PROVISIONAL	item										£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Fire strategy / building control
3B	**Ironmongery (NRM2 24 / package JOI)**														
3B.1	Butt hinges, 100 mm, pairs (1.5 pair per leaf; fire-rated at the flat entrances)	pr		7.50	13.50	6.00			**27.00**			£0.00	£0.00	**£0.00**	1.5 pr per leaf
3B.2	Standard sets: tubular latch, lever pair on roses	set		1.00	5.00				**6.00**			£0.00	£0.00	**£0.00**	All partition doorsets less the privacy sets
3B.3	Bathroom / WC sets: privacy lock, thumb-turn with emergency release, lever pair	set		2.00	2.00	2.00			**6.00**			£0.00	£0.00	**£0.00**	ASSUMED 1 per flat - wet rooms not in the model; adjust to the door schedule
3B.4	Flat entrance sets: multi-point / night latch, lever pair, overhead self-closer, door viewer, numerals	set		2.00	2.00	2.00			**6.00**			£0.00	£0.00	**£0.00**	FD30S
3B.5	Flush bolts (pair of leaves, inactive leaf)	pr							**0.00**			£0.00	£0.00	**£0.00**	Pairs
3B.6	Door stops, floor or skirting mounted	nr		5.00	9.00	4.00			**18.00**			£0.00	£0.00	**£0.00**	One per leaf

External doors, the common entrance and the terrace / balcony doors are in Bill 8 (glazing / external doors).

PACKAGE SUMMARY - Bill 3 Internal Doors, Flat Entrance Doors & Ironmongery (package JOI; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
3A	Internal doorsets (NRM2 24 / package JOI)	£0.00	£0.00	**£0.00**
3B	Ironmongery (NRM2 24 / package JOI)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 3, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 4 - Joinery - Skirtings, Architraves, Window Boards, Stairs & Balustrades

Second-fix joinery measured per level from the model wall faces and the spec openings; the common stair and the Flat 5 stair indicative. [NRM2 22 / package JOI]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the Basis Point Design planning drawings P01-P16 Rev E (10.03.2022, 1:100 @ A3: plans, elevations, sections); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F) / L4 (3F) and the Roof; the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB foundation	L1 GF	L2 1F	L3 2F	L4 3F attic	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	1	6						Levels: FB = foundation: 2 courses (XR35 envelope + Std separating walls), -914 to 0 on the strip footing (by others); L1 = ground floor, Flats 1 / 2: 6 courses 0-2,743 (ceiling at the 1F B&B soffit 2,468); L2 = first floor, Flats 3 / 4 + the bays + the 2-storey wing: 6 courses 2,743-5,486 (soffit 5,211); L3 = second floor, Flats 5 / 6: 6 courses 5,486-8,230 (soffit 7,955); L4 = 3F Flat 5 attic: eaves walls cut at
4A	**Skirtings (NRM2 22 / package JOI)**														
	No room model: every lined wall face at floor level - the ICF inner perimeter less the external / terrace door openings, the separating walls both faces (the stair-core faces at 1F / 2F one side only - the core is a void), TLSTF partitions both faces less their door openings, less the flat entrance doors. 3F: the attic knee walls + the party wall. 18 x 144 torus / ogee MDF (heritage), profile by the client.														
4A.1	Skirting 18 x 144 MDF, primed, fixed to the linings	m		139.58	123.11	88.44	47.94		**399.08**			£0.00	£0.00	**£0.00**	Order guide +10% = 439.0
4B	**Architraves (NRM2 22 / package JOI)**														
	Per face = 2 legs x 2150 + (opening + 2 x 70). Internal and flat entrance doors both faces; external / terrace / balcony doors inside face only (2,350 legs); windows have plastered reveals (no architrave).														
4B.1	Architrave to internal and flat entrance doors, both faces, 18 x 69 (profile by the client)	m		53.66	96.42	42.18			**192.26**			£0.00	£0.00	**£0.00**	Order guide +10% = 211.5
4B.2	Architrave to the external / terrace / balcony doors, inside face	m		23.90	17.18	11.58			**52.66**			£0.00	£0.00	**£0.00**	Order guide +10% = 57.9
4C	**Window boards (NRM2 22 / package JOI)**														
	Every window (sills 457 above FFL per the spec): board = opening + 2 x 50, depth 211 + 25, grouped by opening width.														
4C.1	Window board MDF / timber 236 x 440 long (openings ~340 wide)	nr		1.00	1.00				**2.00**			£0.00	£0.00	**£0.00**	L1-W08, L2-W06
4C.2	Window board MDF / timber 236 x 460 long (openings ~360 wide)	nr		1.00					**1.00**			£0.00	£0.00	**£0.00**	L1-W07
4C.3	Window board MDF / timber 236 x 500 long (openings ~400 wide)	nr		5.00	5.00				**10.00**			£0.00	£0.00	**£0.00**	L1-W10, L1-W11, L1-W13, L1-W17, L1-W19, L2-W08, L2-W09, L2-W11, L2-W16, L2-W18
4C.4	Window board MDF / timber 236 x 600 long (openings ~500 wide)	nr		4.00	3.00	7.00			**14.00**			£0.00	£0.00	**£0.00**	L1-W01, L1-W02, L1-W05, L1-W06, L2-W01, L2-W02, L2-W05, L3-W01, L3-W02, L3-W03, L3-W04, L3-W05, L3-W12, L3-W13
4C.5	Window board MDF / timber 236 x 610 long (openings ~510 wide)	nr				1.00			**1.00**			£0.00	£0.00	**£0.00**	L3-W06
4C.6	Window board MDF / timber 236 x 700 long (openings ~600 wide)	nr		1.00	1.00				**2.00**			£0.00	£0.00	**£0.00**	L1-W14, L2-W12
4C.7	Window board MDF / timber 236 x 780 long (openings ~680 wide)	nr		2.00	2.00				**4.00**			£0.00	£0.00	**£0.00**	L1-W15, L1-W16, L2-W14, L2-W15
4C.8	Window board MDF / timber 236 x 840 long (openings ~740 wide)	nr				1.00			**1.00**			£0.00	£0.00	**£0.00**	L3-W14
4C.9	Window board MDF / timber 236 x 850 long (openings ~750 wide)	nr		1.00		3.00			**4.00**			£0.00	£0.00	**£0.00**	L1-W03, L3-W09, L3-W11, L3-W15
4C.10	Window board MDF / timber 236 x 860 long (openings ~760 wide)	nr		1.00		1.00			**2.00**			£0.00	£0.00	**£0.00**	L1-W04, L3-W07
4C.11	Window board MDF / timber 236 x 1,000 long (openings ~900 wide)	nr		1.00	2.00				**3.00**			£0.00	£0.00	**£0.00**	L1-W12, L2-W10, L2-W13
4C.12	Window board MDF / timber 236 x 1,010 long (openings ~910 wide)	nr		2.00	2.00				**4.00**			£0.00	£0.00	**£0.00**	L1-W09, L1-W18, L2-W07, L2-W17
4C.13	Window board MDF / timber 236 x 1,100 long (openings ~1,000 wide)	nr			1.00	3.00			**4.00**			£0.00	£0.00	**£0.00**	L2-W03, L3-W08, L3-W10, L3-W16
4C.14	Window board MDF / timber 236 x 1,110 long (openings ~1,010 wide)	nr			1.00				**1.00**			£0.00	£0.00	**£0.00**	L2-W04
4D	**Stairs, balustrades and sundry joinery (NRM2 22 / package JOI) - INDICATIVE, not modelled**														
	Common stair in the octagonal stair core (triple volume, GF to 2F): storey height 2,743.2 -> 15 risers of 182.9 (ADK common stair max rise 190, min going 250); Flat 5 private stair 2F to 3F through the 3F floor opening (2.80 m2): 13 risers of 211.0 (private max 220). Geometry by the stair manufacturer / architect.														
4D.1	Common stair flight set, one storey (15 risers x 182.9), to the octagonal core plan (winders / half landings as the architect), incl. strings, treads, risers, nosings - fire / Part K common stair	nr		1.00	1.00				**2.00**			£0.00	£0.00	**£0.00**	GF-1F (L1) and 1F-2F (L2) - PROVISIONAL
4D.2	Handrails both sides + balustrade / guarding 1,100 to the common stair and landings (wrought-iron to suit the heritage look - spec TBC)	item		1.00	1.00				**2.00**			£0.00	£0.00	**£0.00**	Per storey flight - PROVISIONAL
4D.3	Flat 5 private stair 2F to 3F (13 risers x 211.0), incl. handrail + balustrade	nr				1.00			**1.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - through the 3F floor opening
4D.4	Guarding 900 / 1,100 around the Flat 5 stair opening at 3F	item					1.00		**1.00**			£0.00	£0.00	**£0.00**	PROVISIONAL

Ref	Description	Unit	FB foundation	L1 GF	L2 1F	L3 2F	L4 3F attic	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	1	6						Levels: FB = foundation: 2 courses (XR35 envelope + Std separating walls), -914 to 0 on the strip footing (by others); L1 = ground floor, Flats 1 / 2: 6 courses 0-2,743 (ceiling at the 1F B&B soffit 2,468); L2 = first floor, Flats 3 / 4 + the bays + the 2-storey wing: 6 courses 2,743-5,486 (soffit 5,211); L3 = second floor, Flats 5 / 6: 6 courses 5,486-8,230 (soffit 7,955); L4 = 3F Flat 5 attic: eaves walls cut at
4D.5	Eaves-storage access hatches in the 3F knee walls (insulated, draught-sealed) - PROVISIONAL	nr					2.00		**2.00**			£0.00	£0.00	**£0.00**	Not drawn
4D.6	Boxings to services / soil stacks (6 flats) and pipe runs	item										£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Allowance - positions to the M&E design

PACKAGE SUMMARY - Bill 4 Joinery - Skirtings, Architraves, Window Boards, Stairs & Balustrades (package JOI; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
4A	Skirtings (NRM2 22 / package JOI)	£0.00	£0.00	**£0.00**
4B	Architraves (NRM2 22 / package JOI)	£0.00	£0.00	**£0.00**
4C	Window boards (NRM2 22 / package JOI)	£0.00	£0.00	**£0.00**
4D	Stairs, balustrades and sundry joinery (NRM2 22 / package JOI) - INDICATIVE, not modelled	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 4, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 5 - Timber Stud Partitions (TLSTF) - Framing, Openings, Head Restraint & Fixings

Non-loadbearing 38 x 89 C16 timber stud partitions from the TLSTF model (GF 16 walls 33.4 m / 1F 15 walls 33.0 m / 2F 9 walls 17.7 m = 84.1 m, 12 door openings). Linings in Bill 2, doorsets in Bill 3. [NRM2 16 / package JOI]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the Basis Point Design planning drawings P01-P16 Rev E (10.03.2022, 1:100 @ A3: plans, elevations, sections); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F) / L4 (3F) and the Roof; the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB foundation	L1 GF	L2 1F	L3 2F	L4 3F attic	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	1	6						Levels: FB = foundation: 2 courses (XR35 envelope + Std separating walls), -914 to 0 on the strip footing (by others); L1 = ground floor, Flats 1 / 2: 6 courses 0-2,743 (ceiling at the 1F B&B soffit 2,468); L2 = first floor, Flats 3 / 4 + the bays + the 2-storey wing: 6 courses 2,743-5,486 (soffit 5,211); L3 = second floor, Flats 5 / 6: 6 courses 5,486-8,230 (soffit 7,955); L4 = 3F Flat 5 attic: eaves walls cut at 9,144, NE party wall to 11,430, RE = roofs: main hipped roof (gable
5A	**Timber stud partitions, non-loadbearing - framing (NRM2 16 / package JOI)**														
	C16 softwood stud partitions as built in the TLSTF model (GF 16 walls 33.4 m / 1F 15 walls 33.0 m / 2F 9 walls 17.7 m = 84.1 m, 12 door openings): 38 x 89 studs at 600 c/c (400 where built up: bc_int_89_600 40), head and bottom rails, noggins. Each storey FFL to 5 mm under the precast beam soffit of the floor above (2,558.2). Gross area, door openings NOT deducted (5C). Load-bearing / separating walls are ICF (Nudura).														
5A.1	GF partitions (16 walls, 33.4 m x 2,558): 38 x 89 C16 studs, head + bottom rails, noggins	m2		85.40					**85.40**			£0.00	£0.00	**£0.00**	wall length x height
5A.2	1F partitions (15 walls, 33.0 m x 2,558): 38 x 89 C16 studs, head + bottom rails, noggins	m2			84.52				**84.52**			£0.00	£0.00	**£0.00**	wall length x height
5A.3	2F partitions (9 walls, 17.7 m x 2,558): 38 x 89 C16 studs, head + bottom rails, noggins	m2				45.25			**45.25**			£0.00	£0.00	**£0.00**	wall length x height
5B	**Partition timber - supply (NRM2 16 / package JOI)**														
	ESTIMATE in linear metres of 38 x 89 C16 kiln-dried sawn softwood: studs from the TLSTF verify reports (stud counts x stud length 2,520.2), bottom rails (door gaps cut out) + head rails, one noggin row and 2 king studs + head per door. TLSTF members: GF 350, 1F 350, 2F 190. Reconcile against the TLSTF construction extract before ordering. Supply only.														
5B.1	38 x 89 C16 kiln-dried sawn softwood: studs (TLSTF stud counts x stud length)	m		216.74	204.14	115.93			**536.80**			£0.00	£0.00	**£0.00**	Estimate - see 5B note
5B.2	38 x 89 C16 kiln-dried sawn softwood: bottom + head rails	m		63.99	59.68	33.90			**157.57**			£0.00	£0.00	**£0.00**	Estimate - see 5B note
5B.3	38 x 89 C16 kiln-dried sawn softwood: noggins (one row)	m		30.60	26.64	16.21			**73.46**			£0.00	£0.00	**£0.00**	Estimate - see 5B note
5B.4	38 x 89 C16 kiln-dried sawn softwood: king studs and heads at door openings	m		18.13	42.21	11.71			**72.05**			£0.00	£0.00	**£0.00**	Estimate - see 5B note
5B.5	*38 x 89 C16 lengths to order (run +10%, 4.8 m lengths)*	*nr*		*76.00*	*77.00*	*41.00*			*194.00*					not priced	*Ordering guide only - not priced in addition*
5C	**Forming door openings in partitions (NRM2 16 / package JOI)**														
	From the TLSTF door report (12 openings). Per opening: 2 full-height king studs, head at ~2,100, cripples over, bottom rail cut out. Timber in 5B.														
5C.1	Form door opening 554 wide x ~2,100 high in the 89 partition	nr				1.00			**1.00**			£0.00	£0.00	**£0.00**	Doorsets in Bill 3
5C.2	Form door opening 842 wide x ~2,100 high in the 89 partition	nr			1.00				**1.00**			£0.00	£0.00	**£0.00**	Doorsets in Bill 3
5C.3	Form door opening 926 wide x ~2,100 high in the 89 partition	nr		3.00	6.00	1.00			**10.00**			£0.00	£0.00	**£0.00**	Doorsets in Bill 3
5D	**Head restraint, acoustic and fixings (NRM2 16 / package JOI)**														
	Heads: galvanised slotted deflection head clips fixed to the precast B&B soffit with concrete screws (5 mm deflection gap) - TLSTF head-restraint reports (GF 158; 1F 140; 2F 82 clips). No floor noggins / pattress reports this job (precast floors; wet rooms not modelled). Bottom rails fixed down to the screed on a DPC strip.														
5D.1	Slotted deflection head clip, galvanised, partition head rail to the precast soffit (concrete screws; product to confirm)	nr		158.00	140.00	82.00			**380.00**			£0.00	£0.00	**£0.00**	TLSTF head-restraint reports
5D.2	Fix bottom rails: concrete screws to the screed / topping at max 600 c/c on a DPC strip	m		30.60	26.64	16.21			**73.46**			£0.00	£0.00	**£0.00**	Bottom rail length (door gaps excluded)
5D.3	Acoustic mineral wool quilt (min 10 kg/m3, 25 thick) in the partition voids - Part E E2 internal walls (Rw 40) round bedrooms / WCs	m2		85.40	84.52	45.25			**215.17**			£0.00	£0.00	**£0.00**	Allow all partitions - reduce to the architect's room layout
5D.4	Ply / timber pattresses in the stud bays for sanitaryware, kitchen units and wall-hung fittings (wet rooms not modelled)	item										£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Allowance - positions to the kitchen / bathroom layouts
5D.5	Nails, screws, framing fixings and sundries for the partition framing	item										£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount.

PACKAGE SUMMARY - Bill 5 Timber Stud Partitions (TLSTF) - Framing, Openings, Head Restraint & Fixings (package JOI; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
5A	Timber stud partitions, non-loadbearing - framing (NRM2 16 / package JOI)	£0.00	£0.00	**£0.00**
5B	Partition timber - supply (NRM2 16 / package JOI)	£0.00	£0.00	**£0.00**
5C	Forming door openings in partitions (NRM2 16 / package JOI)	£0.00	£0.00	**£0.00**
5D	Head restraint, acoustic and fixings (NRM2 16 / package JOI)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 5, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 6 - Substructure, Precast B&B Floors, Roof Terrace & Steels (coordination)

Coordination quantities for the engineer / groundworker / beam supplier: strip footing, vents, GF / 1F / 2F / 3F precast B&B floors, the 1F roof terrace and the indicative steels. [NRM2 5 / 11 / 14 / 16 / package GRW / FLR / STR]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the Basis Point Design planning drawings P01-P16 Rev E (10.03.2022, 1:100 @ A3: plans, elevations, sections); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F) / L4 (3F) and the Roof; the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB foundation	L1 GF	L2 1F	L3 2F	L4 3F attic	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	1	6						Levels: FB = foundation: 2 courses (XR35 envelope + Std separating walls), -914 to 0 on the strip footing (by others); L1 = ground floor, Flats 1 / 2: 6 courses 0-2,743 (ceiling at the 1F B&B soffit 2,468); L2 = first floor, Flats 3 / 4 + the bays + the 2-storey wing: 6 courses 2,743-5,486 (soffit 5,211); L3 = second floor, Flats 5 / 6: 6 courses 5,486-8,230 (soffit 7,955); L4 = 3F Flat 5 attic: eaves walls cut at 9,144, NE party wall to 11,430; RF = roofs: main hipped roof (gable
6A	**Substructure (NRM2 5 / 11 - package GRW; by others - engineer; coordination quantities)**														
	The ICF FB foundation (2 courses, -914 to 0) stands on a concrete strip footing BY OTHERS (size by the engineer - not in the model), under the XR35 envelope and the 6in Standard separating walls. The suspended GF (precast B&B, beam top -200) needs a ventilated void: underfloor vents / sleeves through the FB must be FORMED BEFORE THE FB POUR. The NE wall is on the boundary with No. 27 Bromfelde Road: Party Wall etc. Act 1996 notices (adjacent excavation) - party wall surveyor. NOT in the Nudura price.														
6A.1	Strip footing under the ICF FB walls (concrete, width / depth / reinforcement by the engineer), incl. starter bars into the ICF core	m	74.74						**74.74**			£0.00	£0.00	**£0.00**	FB centre-line length (envelope + separating walls) - PROVISIONAL, engineer
6A.2	Protection board / DPM to the below-ground FB EPS faces before backfill (ICF-compatible, solvent-free)	m2	50.67						**50.67**			£0.00	£0.00	**£0.00**	Order guide +15% = 58.3
6A.3	Perimeter land drain at footing level (perforated pipe in clean stone, geotextile) - IF required by the site investigation	m	54.56						**54.56**			£0.00	£0.00	**£0.00**	PROVISIONAL
6A.4	GF sleeper walls under the B&B (S1, T1) incl. their footings - by the groundworker / engineer	m	30.38						**30.38**			£0.00	£0.00	**£0.00**	BC_floors.json GF "sleeper wall" lines
6A.5	Telescopic underfloor vents / sleeves through the FB to ventilate the void under the GF B&B (~2 m c/c, per the beam supplier / Part C) - sleeves set in the ICF BEFORE the FB pour	nr	28.00						**28.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - count = perimeter (less the NE party wall) / 2 m
6A.6	Party Wall etc. Act 1996: notices / awards / schedule of condition of No. 27; any underpinning or special foundation at the NE wall	item										£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Party wall surveyor / engineer - PROVISIONAL
6B	**GF floor (FFL 0.0) - precast beam & block BY OTHERS (NRM2 14 / 16 - package FLR; beam supplier design)**														
	As modelled (BC_floors.json): 150 precast B&B (beam top -200, ventilated void below) + DPM / gas membrane + 150 rigid insulation + 50 screed (top = FFL 0). 85 beams 120 x 150 @ 565 (270.2 m, max clear span 4,993 mm, 0 over 5 m) bearing on the ICF core (inner panel cut down at the bearing course - ICF coordination). Indicative - the beam supplier designs the layout.														
6B.1	Precast prestressed beams 120 x 150 (count / total length 270.2 m)	nr		85.00					**85.00**			£0.00	£0.00	**£0.00**	
6B.2	Infill blocks (7 N/mm2 or as the beam supplier), brushed-in grout - floor area	m2		161.89					**161.89**			£0.00	£0.00	**£0.00**	
6B.3	DPM / ground-gas membrane over the B&B, lapped and sealed to the ICF (per the site investigation)	m2		161.89					**161.89**			£0.00	£0.00	**£0.00**	
6B.4	150 rigid PIR / EPS floor insulation	m2		161.89					**161.89**			£0.00	£0.00	**£0.00**	
6B.5	Separating layer + 50 sand / cement or flowing screed (top = FFL)	m2		161.89					**161.89**			£0.00	£0.00	**£0.00**	
6B.6	25 PIR perimeter edge insulation upstand to the screed against the ICF (inner perimeter x 0.2)	m2		12.00					**12.00**			£0.00	£0.00	**£0.00**	
6B.7	Bearings: beam ends bearing on the ICF core (inner panel cut down) - ICF erector coordination	nr		170.00					**170.00**			£0.00	£0.00	**£0.00**	
6C	**1F floor (FFL 2,743.2) - precast beam & block BY OTHERS (NRM2 14 / 16 - package FLR; beam supplier design)**														
	As modelled (BC_floors.json): 150 B&B + 100 concrete topping + 25 levelling screed (separating floor - Part E). 83 beams 120 x 150 @ 565 (253.7 m, max clear span 4,993 mm, 0 over 5 m) bearing on the ICF core (inner panel cut down at the bearing course - ICF coordination). Indicative - the beam supplier designs the layout. Includes the 1F ROOF TERRACE (12.57 m2) over GF Flat 2 - waterproofing / insulation / paving BY OTHERS (6C terrace items).														
6C.1	Precast prestressed beams 120 x 150 (count / total length 253.7 m)	nr			83.00				**83.00**			£0.00	£0.00	**£0.00**	
6C.2	Infill blocks (7 N/mm2 or as the beam supplier), brushed-in grout - floor area	m2			152.59				**152.59**			£0.00	£0.00	**£0.00**	
6C.3	100.0 concrete structural / levelling topping (beam supplier spec)	m2			152.59				**152.59**			£0.00	£0.00	**£0.00**	
6C.4	25 levelling screed (or resilient layer + screed where the acoustic design needs it)	m2			152.59				**152.59**			£0.00	£0.00	**£0.00**	
6C.5	Resilient layer / acoustic treatment to the separating floor (Part E: floating screed or resilient ceiling - acoustician; pre-completion testing)	m2			152.59				**152.59**			£0.00	£0.00	**£0.00**	
6C.6	Bearings: beam ends bearing on the ICF core (inner panel cut down) - ICF erector coordination	nr			166.00				**166.00**			£0.00	£0.00	**£0.00**	
6C.7	Roof terrace over GF Flat 2: warm-roof waterproofing (VCL, tapered PIR, membrane), upstands to the ICF + thresholds of the terrace doors, outlets - BY OTHERS	m2			12.57				**12.57**			£0.00	£0.00	**£0.00**	Coordination - level of the terrace vs the 1F FFL / door thresholds (Part M)
6C.8	Terrace paving on pedestals over the membrane - BY OTHERS	m2			12.57				**12.57**			£0.00	£0.00	**£0.00**	

Ref	Description	Unit	FB foundation	L1 GF	L2 1F	L3 2F	L4 3F attic	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	1	6						Levels: FB = foundation: 2 courses (XR35 envelope + Std separating walls). -914 to 0 on the strip footing (by others); L1 = ground floor, Flats 1 / 2: 6 courses 0-2,743 (ceiling at the 1F B&B soffit 2,468); L2 = first floor, Flats 3 / 4 + the bays + the 2-storey wing: 6 courses 2,743-5,486 (soffit 5,211); L3 = second floor, Flats 5 / 6: 6 courses 5,486-8,230 (soffit 7,955); L4 = 3F Flat 5 attic: eaves walls cut at [illegible]
6C.9	Terrace edge: upstand / parapet + guarding 1,100 (wrought-iron rail to match the balconies) to the open edges	m			7.69				**7.69**			£0.00	£0.00	**£0.00**	Open edges of the terrace polygon (not against the 1F walls)
6D	**2F floor (FFL 5,486.4) - precast beam & block BY OTHERS (NRM2 14 / 16 - package FLR; beam supplier design)**														
	As modelled (BC_floors.json): 150 B&B + 100 concrete topping + 25 levelling screed (separating floor - Part E). 61 beams 120 x 150 @ 565 (188.7 m, max clear span 4,978 mm, 0 over 5 m) bearing on the ICF core (inner panel cut down at the bearing course - ICF coordination). Indicative - the beam supplier designs the layout.														
6D.1	Precast prestressed beams 120 x 150 (count / total length 188.7 m)	nr				61.00			**61.00**			£0.00	£0.00	**£0.00**	
6D.2	Infill blocks (7 N/mm2 or as the beam supplier), brushed-in grout - floor area	m2				112.60			**112.60**			£0.00	£0.00	**£0.00**	
6D.3	100.0 concrete structural / levelling topping (beam supplier spec)	m2				112.60			**112.60**			£0.00	£0.00	**£0.00**	
6D.4	25 levelling screed (or resilient layer + screed where the acoustic design needs it)	m2				112.60			**112.60**			£0.00	£0.00	**£0.00**	
6D.5	Resilient layer / acoustic treatment to the separating floor (Part E: floating screed or resilient ceiling - acoustician; pre-completion testing)	m2				112.60			**112.60**			£0.00	£0.00	**£0.00**	
6D.6	Bearings: beam ends bearing on the ICF core (inner panel cut down) - ICF erector coordination	nr				122.00			**122.00**			£0.00	£0.00	**£0.00**	
6E	**3F floor (FFL 8,229.6) - precast beam & block BY OTHERS (NRM2 14 / 16 - package FLR; beam supplier design)**														
	As modelled (BC_floors.json): 150 B&B + 100 topping + 25 screed (Flat 5 attic floor; separating where over Flat 6). 73 beams 120 x 150 @ 565 (196.3 m, max clear span 4,078 mm, 0 over 5 m) bearing on the ICF core (inner panel cut down at the bearing course - ICF coordination). Indicative - the beam supplier designs the layout. Opening 2.80 m2 for the Flat 5 private stair (trimmer beams).														
6E.1	Precast prestressed beams 120 x 150 (count / total length 196.3 m)	nr					73.00		**73.00**			£0.00	£0.00	**£0.00**	
6E.2	Infill blocks (7 N/mm2 or as the beam supplier), brushed-in grout - floor area	m2					117.09		**117.09**			£0.00	£0.00	**£0.00**	
6E.3	100.0 concrete structural / levelling topping (beam supplier spec)	m2					117.09		**117.09**			£0.00	£0.00	**£0.00**	
6E.4	25 levelling screed (or resilient layer + screed where the acoustic design needs it)	m2					117.09		**117.09**			£0.00	£0.00	**£0.00**	
6E.5	Bearings: beam ends bearing on the ICF core (inner panel cut down) - ICF erector coordination	nr					146.00		**146.00**			£0.00	£0.00	**£0.00**	
6F	**Steels (NRM2 14 - package STR; ENGINEER - INDICATIVE, sections not designed)**														
	Indicative steels in BC_floors.json: S1 / T1 / T2 at 1F incl. the TRANSFER beams under the 1F north wall (T1) and the wing east wall (T2) over the GF Flat 2 living room, and S1 at 2F / 3F - lengths only; sections, bearings, padstones / pockets in the ICF core and the fire protection by the engineer. Pockets / bearing plates in the ICF are formed at the pour of the lift below (coordinate with the ICF erector).														
6F.1	1F steel S1: steel UB (indicative - engineer) - section by the engineer	m			17.01				**17.01**			£0.00	£0.00	**£0.00**	Model line length (2 pieces)
6F.2	1F steel T1: steel UB (indicative - engineer) - section by the engineer	m			11.68				**11.68**			£0.00	£0.00	**£0.00**	Model line length (2 pieces)
6F.3	1F steel T2: steel UB (indicative - engineer) - section by the engineer	m			3.56				**3.56**			£0.00	£0.00	**£0.00**	Model line length (1 piece)
6F.4	2F steel S1: steel UB (indicative - engineer) - section by the engineer	m				16.84			**16.84**			£0.00	£0.00	**£0.00**	Model line length (2 pieces)
6F.5	3F steel S1: steel UB (indicative - engineer) - section by the engineer	m					18.95		**18.95**			£0.00	£0.00	**£0.00**	Model line length (1 piece)
6F.6	Padstones / bearing plates / pocket bearings in the ICF core at the steel ends - formed at the pour of the lift below	nr			10.00	4.00	2.00		**16.00**			£0.00	£0.00	**£0.00**	2 per steel piece - engineer
6F.7	Fire protection to the steels (intumescent / board, 60 min - flats) + packers / beam hangers for the B&B at the steels	m			32.25	16.84	18.95		**68.03**			£0.00	£0.00	**£0.00**	Fire strategy / engineer

PACKAGE SUMMARY - Bill 6 Substructure, Precast B&B Floors, Roof Terrace & Steels (coordination) (package GRW / FLR / STR; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
6A	Substructure (NRM2 5 / 11 - package GRW; by others - engineer; coordination quantities)	£0.00	£0.00	**£0.00**
6B	GF floor (FFL 0.0) - precast beam & block BY OTHERS (NRM2 14 / 16 - package FLR; beam supplier design)	£0.00	£0.00	**£0.00**
6C	1F floor (FFL 2,743.2) - precast beam & block BY OTHERS (NRM2 14 / 16 - package FLR; beam supplier design)	£0.00	£0.00	**£0.00**
6D	2F floor (FFL 5,486.4) - precast beam & block BY OTHERS (NRM2 14 / 16 - package FLR; beam supplier design)	£0.00	£0.00	**£0.00**
6E	3F floor (FFL 8,229.6) - precast beam & block BY OTHERS (NRM2 14 / 16 - package FLR; beam supplier design)	£0.00	£0.00	**£0.00**
6F	Steels (NRM2 14 - package STR; ENGINEER - INDICATIVE, sections not designed)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 6, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 7 - Roofs - Cut Roof Structure, Natural Slate, Bay Roofs, Rainwater, Abutments & Insulation

Main hipped roof (gable to the NE party wall) + hipped wing roof (C24 cut roofs, 33 deg), natural slate, hips / ridges / valley, eaves, rainwater, party-wall and wing abutments, the bay roofs and the insulation. [NRM2 16 / 18 / package RFS / RFC]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the Basis Point Design planning drawings P01-P16 Rev E (10.03.2022, 1:100 @ A3: plans, elevations, sections); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F) / L4 (3F) and the Roof; the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB foundation	L1 GF	L2 1F	L3 2F	L4 3F attic	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	1	6						Levels: FB = foundation: 2 courses (XR35 envelope + Std separating walls), -914 to 0 on the strip footing (by others); L1 = ground floor, Flats 1 / 2: 6 courses 0-2,743 (ceiling at the 1F B&B soffit 2,468); L2 = first floor, Flats 3 / 4 + the bays + the 2-storey wing: 6 courses 2,743-5,486 (soffit 5,211); L3 = second floor, Flats 5 / 6: 6 courses 5,486-8,230 (soffit 7,955); L4 = 3F Flat 5 attic: eaves walls cut at
7A	**Roof structure - cut roofs C24 @ 600 (NRM2 16 - package RFS; roof designer / engineer)**														
	Two cut roofs at 33 deg, natural slate: MAIN hipped roof over the 2F / 3F footprint with a GABLE on the NE party wall to No. 27 (plate top 9,294, rise ~2.71 m -> ridge ~12.00 m above GF FFL, geometric, heel ignored), Flat 5 attic room-in-roof under it (no ceiling ties modelled); WING hipped roof over the 2-storey NW wing abutting the main block (plate ~5,636 ASSUMED, ceiling joists = cold roof); 4 small bay roofs at the 1F head (not modelled). Built by the BCDS RoofStruct (struct_Main 83 + struct_Wing 42 members); counts below are the model members by role - sections are NOT in the struct reports (roof designer). ENGINEER: the main roof hip heads are unpropped ("no prop / girder under it") and the 3F room-in-roof has no ties - a structural ridge / purlins / hip girders are needed (not modelled - no invented posts).														
7A.1	Common rafters C24 @ 600	nr						41.00	**41.00**			£0.00	£0.00	**£0.00**	struct_Main 29 + struct_Wing 12
7A.2	Hip jack rafters C24	nr						46.00	**46.00**			£0.00	£0.00	**£0.00**	struct_Main 38 + struct_Wing 8
7A.3	Valley jack rafters C24	nr						3.00	**3.00**			£0.00	£0.00	**£0.00**	struct_Main 3 + struct_Wing 0
7A.4	Cripple rafters C24	nr						4.00	**4.00**			£0.00	£0.00	**£0.00**	struct_Main 4 + struct_Wing 0
7A.5	Hip rafters (C24, doubled / deeper as the roof designer)	nr						7.00	**7.00**			£0.00	£0.00	**£0.00**	struct_Main 5 + struct_Wing 2
7A.6	Valley rafters C24	nr						1.00	**1.00**			£0.00	£0.00	**£0.00**	struct_Main 1 + struct_Wing 0
7A.7	Ridge boards C24	nr						2.00	**2.00**			£0.00	£0.00	**£0.00**	struct_Main 1 + struct_Wing 1
7A.8	Crown rafters at the hip heads C24	nr						3.00	**3.00**			£0.00	£0.00	**£0.00**	struct_Main 2 + struct_Wing 1
7A.9	Ceiling joists C24 @ 600 (wing - cold roof)	nr						16.00	**16.00**			£0.00	£0.00	**£0.00**	struct_Main 0 + struct_Wing 16
7A.10	Binders C24 (wing ceiling)	nr						1.00	**1.00**			£0.00	£0.00	**£0.00**	struct_Main 0 + struct_Wing 1
7A.11	Props / struts (wing)	nr						1.00	**1.00**			£0.00	£0.00	**£0.00**	struct_Main 0 + struct_Wing 1
7A.12	*Rafters C24 - ESTIMATED total length (main + wing pitched slope area incl. overhangs / 0.6 c/c)*	*m*						*324.20*	*324.20*					*not priced*	*Order guide +10% = 356.6*
7A.13	Wall plate 100 x 150 on the ICF eaves walls (main 3F eaves walls cut at 9,144; wing 1F), bedded and anchored to the ICF core	m			13.60		42.49		**56.09**			£0.00	£0.00	**£0.00**	Order guide +10% = 61.7
7A.14	Holding-down straps / anchors, wall plate to the ICF, at max 2.0 m c/c (ADA) + at the corners	nr			13.00		32.00		**45.00**			£0.00	£0.00	**£0.00**	Spacing per the engineer
7A.15	Rafter fixings: rafter-to-plate / hip / ridge connectors (2 per rafter)	nr						188.00	**188.00**			£0.00	£0.00	**£0.00**	
7A.16	Structural ridge / purlins / hip girders for the main roof (unpropped hip heads; 3F room-in-roof without ceiling ties) - ENGINEER	item										£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. NOT modelled - struct_Main warnings
7A.17	Bay roof framing (4 bays at the 1F head: small hipped roofs on a plate over the bay ICF walls) - PROVISIONAL	nr						4.00	**4.00**			£0.00	£0.00	**£0.00**	Not modelled - 2.40 m2; 2.40 m2; 2.40 m2; 2.38 m2
7B	**Roof coverings, eaves, rainwater and abutments (NRM2 18 / 33 - package RFC)**														
	Slope areas = plan at the fascia line x 1.192 (all planes 33 deg; 300 overhangs at the eaves, none at the gable / abutments): main 140.4 m2 plan -> 167.5 m2, wing 22.7 -> 27.1 m2. Hips / ridges / valley lengths from a straight-skeleton height field of the fascia-line outline (true lengths incl. the rise). Natural slate (materials table - "to preserve street look"), England practice: slates on 25 x 50 battens + counter-battens on a vapour-permeable underlay. No rooflights / PV shown on the planning drawings - none measured.															
7B.1	Natural slate covering (spec TBC; double-lap, copper / stainless nails or hooks) incl. under-eaves / top courses, main + wing	m2						194.52	**194.52**			£0.00	£0.00	**£0.00**	Order guide +10% = 214.0
7B.2	Treated battens 25 x 50 (+ counter-battens) to the slating	m2						194.52	**194.52**			£0.00	£0.00	**£0.00**	Order guide +10% = 214.0
7B.3	Vapour-permeable roof underlay with laps	m2						194.52	**194.52**			£0.00	£0.00	**£0.00**	Order guide +15% = 223.7
7B.4	Ridges: ridge slates / tiles (dry-fix, ventilated)	m						19.14	**19.14**			£0.00	£0.00	**£0.00**	main 16.08 + wing 3.06
7B.5	Hips: lead-rolled or mitred slate hips / hip tiles incl. hip irons (true length)	m						24.07	**24.07**			£0.00	£0.00	**£0.00**	main 3 nr 17.33 + wing 2 nr 6.74
7B.6	Valleys: Code 5 lead valley on valley boards (true length)	m						4.99	**4.99**			£0.00	£0.00	**£0.00**	1 nr
7B.7	Eaves: fascia, ventilated soffit (300 overhang), eaves tray / comb (behind the rendered cornice, 1B.5)	m						58.49	**58.49**			£0.00	£0.00	**£0.00**	main 43.69 + wing 14.80 (fascia line)
7B.8	Eaves gutters (heritage cast-iron look aluminium, ogee) incl. stop ends, outlets, brackets	m						58.49	**58.49**			£0.00	£0.00	**£0.00**	Order guide +5% = 61.4
7B.9	Downpipes from the eaves gutters to the drainage, ~1 per 10 m of gutter - TBC	nr						7.00	**7.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - drainage design

Ref	Description	Unit	FB foundation	L1 GF	L2 1F	L3 2F	L4 3F attic	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	1	6						Levels: FB = foundation: 2 courses (XR35 envelope + Std separating walls), -914 to 0 on the strip footing (by others); L1 = ground floor, Flats 1 / 2: 6 courses 0-2,743 (ceiling at the 1F B&B soffit 2,468); L2 = first floor, Flats 3 / 4 + the bays + the 2-storey wing: 6 courses 2,743-5,486 (soffit 5,211); L3 = second floor, Flats 5 / 6: 6 courses 5,486-8,230 (soffit 7,955); L4 = 3F Flat 5 attic: eaves walls cut at
7B.10	NE party wall (No. 27): junction of the slating with the party wall head / No. 27's roof - fire-stopping at the compartment-wall head (ADB B3) + lead weathering / verge, along the gable rakes	m						10.61	**10.61**			£0.00	£0.00	**£0.00**	Party wall surveyor / architect - PROVISIONAL
7B.11	Wing roof abutment to the main block 2F wall: lead soakers + stepped cover flashing (Code 4) along the raking abutment	m						5.17	**5.17**			£0.00	£0.00	**£0.00**	
7B.12	Bay roofs (4 nr): covering (slate to match, or Code 5 lead - spec TBC) incl. underlay, battens, lead hips	m2						11.42	**11.42**			£0.00	£0.00	**£0.00**	Plan 9.58 m2 x 1.192 (33 deg ASSUMED) - PROVISIONAL
7B.13	Bay roof abutments to the 2F wall above: lead apron / cover flashing	m						12.80	**12.80**			£0.00	£0.00	**£0.00**	
7B.14	Bay roof eaves: fascia / gutter / outlets	m						16.67	**16.67**			£0.00	£0.00	**£0.00**	Bay outer faces
7C	**Roof insulation and VCL (NRM2 18 / 28 - package RFC)**														
	Main roof: WARM pitched roof over the Flat 5 room-in-roof ASSUMED (insulation between + under the rafters, VCL on the warm side) measured on the slope to the ICF inner wall line (110.0 m2 plan); the attic linings are in Bill 2B.4. Wing: COLD roof (ceiling joists) - insulation at the 1F ceiling (12.8 m2 inside the wing walls) with cross-ventilation at the eaves. Build-up and U-values by the SAP assessor (Approved Document L).														
7C.1	Main roof: insulation between the rafters + insulated board under the rafters (warm pitched roof over the attic room)	m2						131.11	**131.11**			£0.00	£0.00	**£0.00**	Order guide +5% = 137.7
7C.2	Main roof: vapour control layer, taped laps and penetrations	m2						131.11	**131.11**			£0.00	£0.00	**£0.00**	Order guide +10% = 144.2
7C.3	Wing (cold roof): 100 between + 200 over the ceiling joists mineral wool quilt, loft boarding / walkway to the access - and the bay ceilings (PROVISIONAL)	m2						12.78	**12.78**			£0.00	£0.00	**£0.00**	Order guide +5% = 13.4
7C.4	Wing eaves ventilation (10 mm continuous) + rafter-ventilation trays	m						14.80	**14.80**			£0.00	£0.00	**£0.00**	
7C.5	Fire stopping / cavity closers at the eaves over the ICF wall heads and at the party-wall head (compartment wall, ADB B3)	item										£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount.

PACKAGE SUMMARY - Bill 7 Roofs - Cut Roof Structure, Natural Slate, Bay Roofs, Rainwater, Abutments & Insulation (package RFS / RFC; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
7A	Roof structure - cut roofs C24 @ 600 (NRM2 16 - package RFS; roof designer / engineer)	£0.00	£0.00	**£0.00**
7B	Roof coverings, eaves, rainwater and abutments (NRM2 18 / 33 - package RFC)	£0.00	£0.00	**£0.00**
7C	Roof insulation and VCL (NRM2 18 / 28 - package RFC)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 7, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 8 - Glazing, External Doors, Common Entrance, Balconies & Guarding

Heritage sash-style windows, external / terrace / balcony doors from the BuildEase window fit, the common entrance, Juliet balconies and window guarding. [NRM2 25 / package WIN / MET]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the Basis Point Design planning drawings P01-P16 Rev E (10.03.2022, 1:100 @ A3: plans, elevations, sections); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F) / L4 (3F) and the Roof; the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB foundation	L1 GF	L2 1F	L3 2F	L4 3F attic	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	1	6						Levels: FB = foundation: 2 courses (XR35 envelope + Std separating walls), -914 to 0 on the strip footing (by others); L1 = ground floor, Flats 1 / 2: 6 courses 0-2,743 (ceiling at the 1F B&B soffit 2,468); L2 = first floor, Flats 3 / 4 + the bays + the 2-storey wing: 6 courses 2,743-5,486 (soffit 5,211); L3 = second floor, Flats 5 / 6: 6 courses 5,486-8,230 (soffit 7,955); L4 = 3F Flat 5 attic: eaves walls cut at
8A	**Windows - white heritage sash-style double-glazed, acoustic, openable (NRM2 25 - package WIN; window supplier)**														
	From the BuildEase window fit (bcw_fit.json, 62 items): structural opening sizes (so). Elevations / materials table: white sash-style "heritage type" high-performance ACOUSTIC double-glazed openable windows (the fit models a generic casement - product by the window supplier); OBSCURE glass to all bathroom windows (planning note - positions to the window schedule); GF internal security shutters (8D). Frames tight to the back of the outer EPS. All windows have a 457 sill above FFL (spec) - ADK guarding / restrictors at the 1F / 2F windows (8D).														
8A.1	White heritage sash-style window 341 x 1,829 so, 1 light, acoustic DGU	nr		1.00	1.00				**2.00**			£0.00	£0.00	**£0.00**	L1-W08, L2-W06
8A.2	White heritage sash-style window 361 x 1,829 so, 1 light, acoustic DGU	nr		1.00					**1.00**			£0.00	£0.00	**£0.00**	L1-W07
8A.3	White heritage sash-style window 401 x 1,829 so, 1 light, acoustic DGU	nr		5.00	5.00				**10.00**			£0.00	£0.00	**£0.00**	L1-W10, L1-W11, L1-W13, L1-W17, L1-W19, L2-W08, L2-W09, L2-W11, L2-W16, L2-W18
8A.4	White heritage sash-style window 500 x 1,372 so, 1 light, acoustic DGU	nr				2.00			**2.00**			£0.00	£0.00	**£0.00**	L3-W12, L3-W13
8A.5	White heritage sash-style window 500 x 1,829 so, 1 light, acoustic DGU	nr		4.00	3.00	5.00			**12.00**			£0.00	£0.00	**£0.00**	L1-W01, L1-W02, L1-W05, L1-W06, L2-W01, L2-W02, L2-W05, L3-W01, L3-W02, L3-W03, L3-W04, L3-W05
8A.6	White heritage sash-style window 511 x 1,829 so, 1 light, acoustic DGU	nr				1.00			**1.00**			£0.00	£0.00	**£0.00**	L3-W06
8A.7	White heritage sash-style window 601 x 1,829 so, 1 light, acoustic DGU	nr		1.00	1.00				**2.00**			£0.00	£0.00	**£0.00**	L1-W14, L2-W12
8A.8	White heritage sash-style window 681 x 1,829 so, 1 light, acoustic DGU	nr		2.00	2.00				**4.00**			£0.00	£0.00	**£0.00**	L1-W15, L1-W16, L2-W14, L2-W15
8A.9	White heritage sash-style window 741 x 1,829 so, 1 light, acoustic DGU	nr				1.00			**1.00**			£0.00	£0.00	**£0.00**	L3-W14
8A.10	White heritage sash-style window 751 x 1,372 so, 1 light, acoustic DGU	nr				1.00			**1.00**			£0.00	£0.00	**£0.00**	L3-W09
8A.11	White heritage sash-style window 751 x 1,829 so, 1 light, acoustic DGU	nr		1.00		2.00			**3.00**			£0.00	£0.00	**£0.00**	L1-W03, L3-W11, L3-W15
8A.12	White heritage sash-style window 761 x 1,372 so, 1 light, acoustic DGU	nr				1.00			**1.00**			£0.00	£0.00	**£0.00**	L3-W07
8A.13	White heritage sash-style window 761 x 1,829 so, 1 light, acoustic DGU	nr		1.00					**1.00**			£0.00	£0.00	**£0.00**	L1-W04
8A.14	White heritage sash-style window 901 x 1,829 so, 1 light, acoustic DGU	nr		1.00	2.00				**3.00**			£0.00	£0.00	**£0.00**	L1-W12, L2-W10, L2-W13
8A.15	White heritage sash-style window 910 x 1,829 so, 1 light, acoustic DGU	nr		2.00	2.00				**4.00**			£0.00	£0.00	**£0.00**	L1-W09, L1-W18, L2-W07, L2-W17
8A.16	White heritage sash-style window 1,001 x 1,372 so, 1 light, acoustic DGU	nr				3.00			**3.00**			£0.00	£0.00	**£0.00**	L3-W08, L3-W10, L3-W16
8A.17	White heritage sash-style window 1,001 x 1,829 so, 1 light, acoustic DGU	nr			1.00				**1.00**			£0.00	£0.00	**£0.00**	L2-W03
8A.18	White heritage sash-style window 1,010 x 1,829 so, 1 light, acoustic DGU	nr			1.00				**1.00**			£0.00	£0.00	**£0.00**	L2-W04
8A.T	**Windows - total structural opening area**	**m2**		**19.94**	**20.93**	**17.18**			**58.05**					*not priced*	
8B	**External doors, terrace / balcony doors and the common entrance (NRM2 25 - package WIN)**														
8B.1	Composite external door (48 slab, multi-point lock, vision panel), 901 x 2,287 so	nr		1.00					**1.00**			£0.00	£0.00	**£0.00**	L1-D04; PAS 24 / Approved Document Q
8B.2	Composite external door (48 slab, multi-point lock, vision panel), 1,001 x 2,287 so	nr		1.00					**1.00**			£0.00	£0.00	**£0.00**	L1-D02; PAS 24 / Approved Document Q
8B.3	Glazed double doors / lift-and-slide to the garden (PPC, low threshold), 1,741 x 2,287 so	nr		1.00					**1.00**			£0.00	£0.00	**£0.00**	L1-D01; PAS 24 / Approved Document Q
8B.4	Aluminium glazed door + sidelight to the terrace / Juliet balcony (PPC, low threshold), 751 x 2,287 so	nr			1.00				**1.00**			£0.00	£0.00	**£0.00**	L2-D01; PAS 24 / Approved Document Q
8B.5	Aluminium glazed door + sidelight to the terrace / Juliet balcony (PPC, low threshold), 901 x 2,287 so	nr		1.00		1.00			**2.00**			£0.00	£0.00	**£0.00**	L1-D03, L3-D01; PAS 24 / Approved Document Q
8B.6	Aluminium glazed door + sidelight to the terrace / Juliet balcony (PPC, low threshold), 910 x 2,287 so	nr			1.00				**1.00**			£0.00	£0.00	**£0.00**	L2-D02; PAS 24 / Approved Document Q
8B.7	Aluminium glazed door + sidelight to the terrace / Juliet balcony (PPC, low threshold), 1,001 x 2,287 so	nr			1.00	1.00			**2.00**			£0.00	£0.00	**£0.00**	L2-D03, L3-D02; PAS 24 / Approved Document Q

Ref	Description	Unit	FB foundation	L1 GF	L2 1F	L3 2F	L4 3F attic	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	1	6						Levels: FB = foundation: 2 courses (XR35 envelope + Std separating walls), -914 to 0 on the strip footing (by others); L1 = ground floor, Flats 1 / 2: 6 courses 0-2,743 (ceiling at the 1F B&B soffit 2,468); L2 = first floor, Flats 3 / 4 + the bays + the 2-storey wing: 6 courses 2,743-5,486 (soffit 5,211); L3 = second floor, Flats 5 / 6: 6 courses 5,486-8,230 (soffit 7,955); L4 = 3F Flat 5 attic: eaves walls cut at
8B.8	Common entrance (stair core, Union Road): upgrade to the DOUBLE-HEIGHT glazed entrance door + screen and the tall stair-core window bay as drawn ("treated to avoid a lighthouse effect"), door-entry / intercom, Part M level access - PROVISIONAL	item		1.00					**1.00**			£0.00	£0.00	**£0.00**	Elevations P13 - architect
8C	**Balconies, Juliet balconies and the terrace doors (NRM2 25 / 22 - package MET)**														
8C.1	Juliet balcony / guarding 1,100 to the upper-floor glazed doors not onto the terrace (wrought iron - materials table), fixed into the ICF	nr			1.00	2.00			**3.00**			£0.00	£0.00	**£0.00**	L2-D03, L3-D01, L3-D02 (spec)
8C.2	Terrace doors onto the 1F roof terrace - threshold / upstand coordination with the terrace waterproofing (Bill 6C)	nr			2.00				**2.00**			£0.00	£0.00	**£0.00**	L2-D01, L2-D02 (spec)
8D	**Items not modelled (PROVISIONAL)**														
8D.1	Guarding to the windows with a sill below 800 above the floor (ADK K2 / Part K: fixed laminated lower pane, guard rail or restrictors with child-safe release + escape windows per ADB) - 1F / 2F	nr			18.00	16.00			**34.00**			£0.00	£0.00	**£0.00**	Architect - all spec sills 457
8D.2	GF internal security shutters to the windows (materials table: "ground floor internal shutters for security")	nr		19.00					**19.00**			£0.00	£0.00	**£0.00**	PROVISIONAL
8D.3	Trickle / background ventilators or MVHR strategy (Approved Document F) and overheating check (Approved Document O - London, acoustic windows closed) - window supplier / M&E	nr		19.00	18.00	16.00			**53.00**			£0.00	£0.00	**£0.00**	One per window - PROVISIONAL

PACKAGE SUMMARY - Bill 8 Glazing, External Doors, Common Entrance, Balconies & Guarding (package WIN / MET; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
8A	Windows - white heritage sash-style double-glazed, acoustic, openable (NRM2 25 - package WIN; window supplier)	£0.00	£0.00	**£0.00**
8B	External doors, terrace / balcony doors and the common entrance (NRM2 25 - package WIN)	£0.00	£0.00	**£0.00**
8C	Balconies, Juliet balconies and the terrace doors (NRM2 25 / 22 - package MET)	£0.00	£0.00	**£0.00**
8D	Items not modelled (PROVISIONAL)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 8, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Schedule A - Areas: External Faces, Lining Zones, Floor

ICF face areas by finish / zone (component export), floor / ceiling / roof areas (BC_floors +

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the Basis Point Design planning drawings P01-P16 Rev E (10.03.2022, 1:100 @ A3: plans, elevations, sections); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F) / L4 (3F) and the Roof; the Site total is their sum. Rates and amounts are by others.

Level	Item	Source	Length m	Depth / width m	Area m2
FB	FB outer faces (XR35 envelope)	BC_components.json			71.83
FB	FB exposed plinth band, ground ~-150 to FFL (Bill 1A.2)	components	54.56	0.15	8.48
FB	FB below-ground outer faces (protection / DPM, Bill 6A.2)	components			50.67
L1	GF (Flats 1 / 2) outer faces - gault brick slips	components			126.45
L1	GF (Flats 1 / 2) outer faces - NE party wall (No. 27)	components	8.30		21.96
L2	1F (Flats 3 / 4) outer faces - gault brick slips	components			133.16
L2	1F (Flats 3 / 4) outer faces - NE party wall (No. 27)	components	8.30		22.22
L3	2F (Flats 5 / 6) outer faces - gault brick slips	components			96.00
L3	2F (Flats 5 / 6) outer faces - NE party wall (No. 27)	components	8.30		21.88
L4	3F (Flat 5 attic) outer faces - gault brick slips	components			38.84
L4	3F (Flat 5 attic) outer faces - NE party wall (No. 27)	components	8.30		20.26
L1	Lining zone GF (Flats 1 / 2) ICF envelope inner faces	components			112.72
L1	Separating walls GF (Flats 1 / 2) both faces	components	13.30		65.62
L2	Lining zone 1F (Flats 3 / 4) ICF envelope inner faces	components			122.21
L2	Separating walls 1F (Flats 3 / 4) both faces	components	11.89		58.61
L3	Lining zone 2F (Flats 5 / 6) ICF envelope inner faces	components			96.62
L3	Separating walls 2F (Flats 5 / 6) both faces	components	11.24		55.41
L4	Lining zone 3F (Flat 5 attic) ICF envelope inner faces	components			56.64
L1	GF precast B&B floor (beam-supplier outline)	BC_floors.json			161.89
L2	1F precast B&B floor (beam-supplier outline)	BC_floors.json			152.59
L3	2F precast B&B floor (beam-supplier outline)	BC_floors.json			112.60
L4	3F precast B&B floor (beam-supplier outline)	BC_floors.json			117.09
L2	1F roof terrace over GF Flat 2	BC_floors.json	7.69		12.57
L1	GF ceiling = 1F floor inside the ICF less walls / partitions	derived			132.99
L2	1F ceilings = 2F floor + wing / bay rooms less walls	derived			116.73
L2	of which rooms under the wing / bay roofs	derived			18.39
L3	2F ceiling = 3F floor (incl. the stair-core top) less walls	derived			102.13
L4	Flat 5 attic plan inside the ICF	derived	47.94		109.96
L4	Flat 5 attic linings ON THE SLOPE (plan x 1.192)	derived			131.11
all	Stair core (centre lines of the separating walls)	BC_spec party_core			8.93

Level	Item	Source	Length m	Depth / width m	Area m2
L1	Building outline GF (ICF outer faces)	BC_spec chains	62.86		171.36
L3	Building outline 2F / 3F (ICF outer faces)	BC_spec chains	50.79		127.51
RF	Main roof plan at the fascia line (300 overhang, no overhang at the NE gable)	outline	43.69		140.44
RF	Main roof ON THE SLOPE (slate)	derived			167.46
RF	Wing roof plan at the fascia line	outline	14.80		22.70
RF	Wing roof ON THE SLOPE (slate)	derived			27.06
RF	Bay roofs (4) plan	outline 1F outside 2F	16.67		9.58
RF	Wing ceiling insulation (inside the wing walls)	derived			12.78

Ground ASSUMED ~150 below GF FFL all round. The NE party wall faces (No. 27) are listed separately from the brick-slip faces.

Schedule B - Openings Schedule (spec openings + BuildEase window fit)

From BC_spec.json (62 ICF openings) and bcw_fit.json (62 fitted items). Not priced.

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the Basis Point Design planning drawings P01-P16 Rev E (10.03.2022, 1:100 @ A3: plans, elevations, sections); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F) / L4 (3F) and the Roof; the Site total is their sum. Rates and amounts are by others.

Level	Ref	Type	Fit style	W mm	H mm	Sill mm	Area m2	Fit so (W x H)	Source
L1	L1-W01	window	window	500	1829	457	0.91	500 x 1829	plan gap
L1	L1-W02	window	window	500	1829	457	0.91	500 x 1829	plan gap
L1	L1-W03	window	window	750	1829	457	1.37	751 x 1829	plan gap
L1	L1-W04	window	window	760	1829	457	1.39	761 x 1829	plan gap
L1	L1-W05	window	window	500	1829	457	0.91	500 x 1829	plan gap
L1	L1-D01	door	double_door	1740	2286	0	3.98	1741 x 2287	plan gap
L1	L1-D02	door	composite_door	1000	2286	0	2.29	1001 x 2287	plan gap
L1	L1-W06	window	window	500	1829	457	0.91	500 x 1829	plan gap
L1	L1-D03	door	glazed_door	900	2286	0	2.06	901 x 2287	plan gap
L1	L1-W07	window	window	360	1829	457	0.66	361 x 1829	plan gap
L1	L1-W08	window	window	340	1829	457	0.62	341 x 1829	bay / resized for 21
L1	L1-W09	window	window	910	1829	457	1.66	910 x 1829	bay
L1	L1-W10	window	window	400	1829	457	0.73	401 x 1829	bay
L1	L1-W11	window	window	400	1829	457	0.73	401 x 1829	plan gap
L1	L1-W12	window	window	900	1829	457	1.65	901 x 1829	plan gap
L1	L1-W13	window	window	400	1829	457	0.73	401 x 1829	plan gap
L1	L1-W14	window	window	600	1829	457	1.10	601 x 1829	plan gap
L1	L1-D04	door	composite_door	900	2286	0	2.06	901 x 2287	plan gap
L1	L1-W15	window	window	680	1829	457	1.24	681 x 1829	plan gap / resized f

Level	Ref	Type	Fit style	W mm	H mm	Sill mm	Area m2	Fit so (W x H)	Source
L1	L1-W16	window	window	680	1829	457	1.24	681 x 1829	plan gap / resized f
L1	L1-W17	window	window	400	1829	457	0.73	401 x 1829	plan gap
L1	L1-W18	window	window	910	1829	457	1.66	910 x 1829	plan gap
L1	L1-W19	window	window	400	1829	457	0.73	401 x 1829	plan gap
L2	L2-W01	window	window	500	1829	457	0.91	500 x 1829	plan gap
L2	L2-W02	window	window	500	1829	457	0.91	500 x 1829	plan gap
L2	L2-W03	window	window	1000	1829	457	1.83	1001 x 1829	plan gap
L2	L2-W04	window	window	1010	1829	457	1.85	1010 x 1829	plan gap
L2	L2-D01	door	glazed_door	750	2286	0	1.71	751 x 2287	plan gap
L2	L2-W05	window	window	500	1829	457	0.91	500 x 1829	plan gap / clear of
L2	L2-D02	door	glazed_door	910	2286	0	2.08	910 x 2287	plan gap
L2	L2-D03	door	glazed_door	1000	2286	0	2.29	1001 x 2287	plan gap
L2	L2-W06	window	window	340	1829	457	0.62	341 x 1829	plan gap / resized f
L2	L2-W07	window	window	910	1829	457	1.66	910 x 1829	plan gap
L2	L2-W08	window	window	400	1829	457	0.73	401 x 1829	bay
L2	L2-W09	window	window	400	1829	457	0.73	401 x 1829	plan gap
L2	L2-W10	window	window	900	1829	457	1.65	901 x 1829	plan gap
L2	L2-W11	window	window	400	1829	457	0.73	401 x 1829	plan gap
L2	L2-W12	window	window	600	1829	457	1.10	601 x 1829	plan gap
L2	L2-W13	window	window	900	1829	457	1.65	901 x 1829	plan gap
L2	L2-W14	window	window	680	1829	457	1.24	681 x 1829	plan gap / resized f
L2	L2-W15	window	window	680	1829	457	1.24	681 x 1829	plan gap / resized f
L2	L2-W16	window	window	400	1829	457	0.73	401 x 1829	plan gap
L2	L2-W17	window	window	910	1829	457	1.66	910 x 1829	plan gap
L2	L2-W18	window	window	400	1829	457	0.73	401 x 1829	plan gap
L3	L3-W01	window	window	500	1829	457	0.91	500 x 1829	plan gap
L3	L3-W02	window	window	500	1829	457	0.91	500 x 1829	plan gap

Level	Ref	Type	Fit style	W mm	H mm	Sill mm	Area m2	Fit so (W x H)	Source
L3	L3-D01	door	glazed_door	900	2286	0	2.06	901 x 2287	plan gap
L3	L3-W03	window	window	500	1829	457	0.91	500 x 1829	plan gap
L3	L3-W04	window	window	500	1829	457	0.91	500 x 1829	plan gap
L3	L3-D02	door	glazed_door	1000	2286	0	2.29	1001 x 2287	plan gap / shifted -
L3	L3-W05	window	window	500	1829	457	0.91	500 x 1829	plan gap
L3	L3-W06	window	window	510	1829	457	0.93	511 x 1829	plan gap
L3	L3-W07	window	window	760	1372	914	1.04	761 x 1372	plan gap / sill 914
L3	L3-W08	window	window	1000	1372	914	1.37	1001 x 1372	plan gap / sill 914
L3	L3-W09	window	window	750	1372	914	1.03	751 x 1372	plan gap / sill 914
L3	L3-W10	window	window	1000	1372	914	1.37	1001 x 1372	plan gap / sill 914
L3	L3-W11	window	window	750	1829	457	1.37	751 x 1829	plan gap
L3	L3-W12	window	window	500	1372	914	0.69	500 x 1372	plan gap / clear of
L3	L3-W13	window	window	500	1372	914	0.69	500 x 1372	plan gap / sill 914
L3	L3-W14	window	window	740	1829	457	1.35	741 x 1829	plan gap
L3	L3-W15	window	window	750	1829	457	1.37	751 x 1829	plan gap
L3	L3-W16	window	window	1000	1372	914	1.37	1001 x 1372	plan gap / sill 914

Spec heads 2,286 above FFL; window sills 457 (spec), doors 0. "not fitted" / "fit only" rows = the fit and the spec are out of step (re-run the fit).

Schedule C - Key Quantities per Level

Reference only - the bills carry the priced quantities. Not priced.

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the Basis Point Design planning drawings P01-P16 Rev E (10.03.2022, 1:100 @ A3: plans, elevations, sections); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F) / L4 (3F) and the Roof; the Site total is their sum. Rates and amounts are by others.

Level	ICF outer face m2	ICF inner face m2	External finish m2	Wall linings m2	Ceilings m2	Door leaves nr	Skirting m	Partitions m2
FB	71.83	64.75	8.48	0.00	0.00	0	0.00	0.00
L1	186.44	163.59	126.45	359.28	132.99	5	139.58	85.40
L2	189.28	170.12	133.16	342.78	116.73	9	123.11	84.52
L3	150.00	139.13	96.00	251.94	102.13	4	88.44	45.25
L4	59.10	56.64	38.84	56.64	131.11	0	47.94	0.00
RF	0.00	0.00	0.00	0.00	0.00	0	0.00	0.00
Total	**656.65**	**594.23**	**402.93**	**1,010.64**	**482.96**	**18.00**	**399.07**	**215.17**

ICF faces from the Report Tool component export (1181 forms; inner + outer incl. the Std separating walls). External finish: FB = plinth band; L1-L4 = brick slips (excl. the NE party wall). L4 ceilings = attic on the slope.

Schedule D - TLSTF Partition Schedule (as built in the model)

From the TLSTF walls / verify / doors / head-restraint reports (04_Logs/build/BC/BCP_*). Not priced.

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the Basis Point Design planning drawings P01-P16 Rev E (10.03.2022, 1:100 @ A3: plans, elevations, sections); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F) / L4 (3F) and the Roof; the Site total is their sum. Rates and amounts are by others.

Floor	Wall	Length mm	Height mm	Area m2	Build-up	Studs	Members	Door openings (mm)	Head clips
GF	GF-P01	689	2,558	1.76	bc_int_89_600	3	11		6
GF	GF-P02	2517	2,558	6.44	bc_int_89_600	6	23		12
GF	GF-P03	3428	2,558	8.77	bc_int_89_600	8	31		14
GF	GF-P04	2592	2,558	6.63	bc_int_89_600	6	23		12
GF	GF-P05	1516	2,558	3.88	bc_int_89_600	5	19		8
GF	GF-P06	656	2,558	1.68	bc_int_89_600	3	11		6
GF	GF-P07	3448	2,558	8.82	bc_int_89_600	6	28	926	14
GF	GF-P08	2415	2,558	6.18	bc_int_89_600	6	23		10
GF	GF-P09	974	2,558	2.49	bc_int_89_600	4	15		6
GF	GF-P10	1788	2,558	4.58	bc_int_89_600	4	17	926	8
GF	GF-P11	967	2,558	2.47	bc_int_89_600	4	15		6
GF	GF-P12	836	2,558	2.14	bc_int_89_600	3	11		6
GF	GF-P13	4170	2,558	10.67	bc_int_89_600	9	47	926	16
GF	GF-P14	3865	2,558	9.89	bc_int_89_600	10	42		16
GF	GF-P15	1504	2,558	3.85	bc_int_89_600	4	15		8
GF	GF-P16	2016	2,558	5.16	bc_int_89_600	5	19		10
1F	1F-P01	690	2,558	1.77	bc_int_89_600	3	11		6
1F	1F-P02	3799	2,558	9.72	bc_int_89_600	8	36	926	14
1F	1F-P03	4491	2,558	11.49	bc_int_89_600	8	36	926	16
1F	1F-P04	2632	2,558	6.73	bc_int_89_600	6	23		12
1F	1F-P05	1516	2,558	3.88	bc_int_89_600	5	19		8

Floor	Wall	Length mm	Height mm	Area m2	Build-up	Studs	Members	Door openings (mm)	Head clips
1F	1F-P06	2077	2,558	5.31	bc_int_89_600	5	26	926	8
1F	1F-P07	1654	2,558	4.23	bc_int_89_600	4	19	926	6
1F	1F-P08	1466	2,558	3.75	bc_int_89_600	4	16	926	6
1F	1F-P09	2412	2,558	6.17	bc_int_89_600	6	23		10
1F	1F-P10	2396	2,558	6.13	bc_int_89_600	6	23		10
1F	1F-P11	1194	2,558	3.05	bc_int_89_600	4	18		6
1F	1F-P12	3027	2,558	7.74	bc_int_89_600	5	32	926, 842	10
1F	1F-P13	870	2,558	2.23	bc_int_89_600	4	15		6
1F	1F-P14	2508	2,558	6.42	bc_int_89_600	7	30		12
1F	1F-P15	2309	2,558	5.91	bc_int_89_600	6	23		10
2F	2F-P01	1063	2,558	2.72	bc_int_89_600	4	15		6
2F	2F-P02	826	2,558	2.11	bc_int_89_600	3	11		6
2F	2F-P03	1912	2,558	4.89	bc_int_89_600	5	19		10
2F	2F-P04	1168	2,558	2.99	bc_int_89_600	4	15		6
2F	2F-P05	3104	2,558	7.94	bc_int_89_600	6	26	554	12
2F	2F-P06	2344	2,558	6.00	bc_int_89_600	6	23		10
2F	2F-P07	3410	2,558	8.72	bc_int_89_600	8	31		14
2F	2F-P08	1692	2,558	4.33	bc_int_89_600	5	19		8
2F	2F-P09	2171	2,558	5.55	bc_int_89_600	5	31	926	10

GF 16 walls 33.4 m / 1F 15 walls 33.0 m / 2F 9 walls 17.7 m = 84.1 m, 12 door openings. Heights: each storey FFL to 5 mm under the precast beam soffit of the floor above.